

SCHEULE – B (Format for Financial Bid)**Rate List/ Quantity Schedule**

Name of the work: Improvement of Panjtarni Camp by way of construction of Pucca foot paths in between tentage area, providing / laying of PVC pipes lines , construction of soakage pits, repairs and erection of toilets/ baths before yatra including maintenance during Yatra period and dismantling of Toilets/ baths after culmination of Yatra-2020.

S. No.01**Adv. Amount = Rs 6.80 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate as per SSR of 2012 in Rs	Rate to be quoted by the Bidder (in Rs)	Amount (in Rs)
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means including removal of rotten/rusted (damaged) base from site and disposal of excavated earth at designated site including leads and lifts, disposed earth is to be levelled and neatly dressed in all kinds of soil.	123.00	Cum	240.45		
2	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish lead upto 50 m and lift upto 1.5 m in all kinds of soil.	114	100 Sqm	1135.95		
3	Providing and laying in position cement concrete of specified grade excluding cost of centring and shuttering all works upto plinth level. a) 1:3:6(1 cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size) nallah stone .	7.216	Cum	3552.50		

	b) 1:4:8(1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size) nallah stone.	8.512	cum	3061.30		
4	Cement concrete pavement with 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate-20 mm nominal size) including finishing complete. Nallah	5.70	cum	5627.80		
5	Dry random rubble masonry with hard stone in foundation and plinth with nallah stone without bond stones.	74.00	Cum	1304.45		
6	Centring and shuttering including strutting, propping etc. and removal of form for- a) Suspended floors, roofs, landings, balconies and access platform. b) Foundations, footings, bases of columns etc. c) Edges of slabs and breaks in floors and walls under 20cms wide.	13.30	Sqm	372.40		
		81.68	Sqm	179.25		
		47.90	Rm	176.55		
7	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	3.65	Cum	5776.45		

8	Reinforcement with RCC work including straightening, cutting, bending, placing in partition and binding all complete TMT Bars	175	Kg	71.00		
9	Supply of skilled and semi-skilled labour for fixing of PVC Pipes and fittings in sewer line a) Plumber/Fitter b) Helper/Asst Fitter	06 06	Each Each	450.00 400.00		
10	Supply and fixing of PVC pipes and other fittings items to toilets/baths 10.1 PVC pipes(110mm) 10.2 PVC bends(110mm) 10.3 D/Bend (110mm) 10.4 Sockets(110mm) 10.5 PVC Tee(110 mm)	88 22 10 22 44	Rm Each Each Each Each	RTQ RTQ RTQ RTQ RTQ		
11	Assembling of toilets/baths at designated site (before commencement of Yatra) including:- i. Carriage of prefabricated panels and other parts from store to site of installation by head load. ii. Minor repairs such as denting, welding & fixing of aldrops and handles etc including supply iii. Supply of nuts & bolts etc of required size. iv. Maintenance of toilet/baths during yatra. v. Excavation/ repair to the cess pits including covering of the same with the available material in SASB store. (Complete Job)	40	Each	RTQ		

12	Dismantling of toilets/baths at erection site including carriage of material from erection site to store with proper stacking after conclusion of Yatra.	40	Each	RTQ		
13	Fixing of CGI sheet roofing to Toilets/Baths with nuts and bolts/J hooks including minor repairs before commencement of yatra including carriage of CGI sheet from SASB store and dismantling of CGI sheet roofing after culmination including carriage and safe storage in SASB stores.	250	Each	RTQ		
14	Carriage of cement(&steel) by MT from Ganderbal to Baltal for an avg lead of 70 Km.	6.456	MT	475.81		
15	Carriage of sand and bajri by head load for an average lead of 0.5 Km.	33.82	cum	279.33		
16	Carriage of cement (and/or steel) by head load for an average lead of 12 Km. 16.1 Ponies: 16.2 Porters:	65 19	Each Each	RTQ RTQ		
17	Carriage of stones by head load for an avg lead of 1Km	74.00	cum	571.17		
Total cost of bid (to be quoted both in figures and words)						

Junior Engineer

DGM (B)

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work:- Assembling /erection of Toilets/ Baths including repairs and construction of soakage pits enroute Dardkote to Poshpathri before Yatra and dismantling the same after conclusion of Yatra -2020

S.No :02

Adv. Amount: Rs 2.37 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (in Rs)	Amount (in Rs)
I	II	III	IV	V	VI	VII
1	Assembling of toilets/baths at designated site (before commence of Yatra) including:- i. Carriage of prefabricated panels and other parts from store to site of installation by head load. ii. Supply of nuts & bolts etc of required size and quantity iii. Fixing of disposal PVC pipe, bends, tee etc and laying the pipes upto nearest sokage pit. (Complete Job)	50	Each	RTQ		
2	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth at designated site including all leads and lifts, disposed earth is to be	73.10	Cum	240.45		

	leveled and neatly dressed in all kinds of soil					
3	Dry random rubble masonry with hard stone in foundation and plinth with nallah stone without bond stone	49.32	Cum	1304.45		
4	Providing and laying of 1:2:4 Reinforced cement concrete excluding the cost of centering, shuttering and reinforcement.	3.65	Cum	4810.70		
5	Centering and shuttering including strutting, propping and removal of formwork for:-					
5.1	For edges of slabs and breaks in flooring (under 20 cm wide)	47.90	Rm	176.55		
5.2	suspended floors, roofs, landing, balconies and access platforms.	13.30	Sqm	372.40		
6	Reinforcement with RCC work including straightening, cutting, bending, placing in partition and binding all complete. TMT Bars.	150.00	kgs	71.00		
7	Carriage of material by Mechanical Transport from Ganderbal to Dumail/Baltal for an avg. lead 70 km	1.32	MT	475.80		
8	Carriage of cement and other materials like PVC pipes and fittings (2 Bags / Pony) and reinforcement by head load from Baltal to Dardkote/Poshpathri for					

	an avg. lead of 18 km i. Ponies ii. Porters	15 04	Each Each	RTQ RTQ		
9	Carriage of sand and bajri by head load for an average lead of 6 Km .	4.92	Cum	2543.53		
10	Carriage of stones by head load for an avg. lead of 1 km in all directions.	49.32	Cum	471.17		
11	Dismantling of toilets/baths at erection site including carriage of material from erection site to store with proper stacking after conclusion of Yatra.	50	Each	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Junior Engineer

DGM (B)

Signature of the Bidder