

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Up-gradation of paths at (A-block) tentage area by way of providing of Cement concrete tiles at Nunwan Camp

S.No: 01

Adv. Amount: Rs. 2.38 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	II	III	IV	V	VI
1	Providing and laying in position cement concrete of specified grade excluding cost of centering and shuttering all works up to plinth level in 1:4:8(1 cement :4 coarse sand : 8 graded stone aggregate 40 mm nominal size) nallah stone	16.75	Cum	4419.85	
2	Providing & fixing of Chequered pre cast tiles 22 mm thick in foot paths and court yards joined with neat cement mortar on 20 mm cement mortar bed in (1:4) mix.	126	sqm	853.45	
3	Providing and laying of concrete band on sides of paths in (1:2:4) mix	2	cum	5877.45	
4	Centering and shuttering including strutting, propping etc. removal of frame work for foundations, footings, bases of columns etc. for mass concrete.	40.75	sqm	262.3	
5	Carriage of material by mechanical transport from Anantnag to Nunwan tiles and cement.				
	sand and aggregates from 50 KMs	28	cum	609.02	
	Cement from 20 kms	7	Mt	386.64	
	Part B				
6	Tiles from Anantnag to Pahalgam	3	trip	RTQ	
	Total cost of bid (to be quoted in figures and words)				

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Up-gradation to store area by way of providing cement concrete flooring 50 mm to accumulate the arrest of ground water which affects the stored assets of Nunwan Camp.

S.No: 02

Adv. Amount: Rs. 1.91 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	II	III	IV	V	VI
1	Providing and fixing of glass strips in joints of terrazzo/cement concrete floor 40 mm wide and 4mm thick	200	Rm	68.25	
2	Cement concrete flooring in (1:2:4) mix by using 20 mm (50 mm thick) Nominal size crushed Agg.	315	sqm	505	
3	Providing and laying in position cement concrete of specified grade excluding cost of centering and shuttering all works upto plinth level in 1:3:6 mix , Path from drain to store.	0.5	cum	4943.4	
4	Carriage of material by mechanical transport from Anantnag to Nunwan from 50 kms for				
	i. sand and aggregates from 50 KMs	21.93	cum	609.02	
	Cement from 20 kms	6.47	Mt	386.64	
Total cost of bid (to be quoted in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)

Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Installation of PPGI sheets shed adjoining to Hut B-1 for proper storing of costing items at Nunwan Camp.

S.No: 03

Adv. Amount: Rs. 1.38 lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	II	III	IV	V	VI
1	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil	0.78	cum	436	
2	Providing and laying in position cement concrete of specified grade excluding cost of centering and shuttering all works up to plinth level in 1:4:8 (1 cement :4 coarse sand : 8 graded stone aggregate 40 mm crushed aggregate.	0.51	cum	4419.85	
3	Providing and laying in position cement concrete of specified grade excluding cost of centering and shuttering all works up to plinth level in 1:3:6 (1 cement :3 coarse sand : 6 graded stone aggregate 20 mm crushed aggregate	1.34	cum	4943.4	
4	Supply and dumping of soling stones as base course with leveling and compacting etc. complete.	5.26	cum	816.4	
5	Providing and laying in position Cement concrete flooring of specified grade in (1:2:4) mix finished without (floating coat of neat cement including cement slurry) but excluding cost of noising the steps etc.	20.8	sqm	505	
6	Centering and shuttering including strutting, propping etc. removal of frame work for foundations, footings, bases of columns etc. for mass concrete.	6.7	sqm	262.3	
7	Providing and fixing pre coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50mm+/- 5% total coated thickness (TCT), Zinc coating 120gsm. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal or with polymer coated J or L hooks bolts and nuts 8mm diameter with bitumen and G.I limpet complete upto pitch in horizontal/ vertical curved surface excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required	68.4	sqm	626.6	

8	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. With ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. 35 mm thick door including aldrops, tower bolts etc, complete,	3.02	sqm	3187.85	
9	Carriage of material by mechanical transport from Anantnag to Nunwan including loading and unloading complete				
	i.Wood from 50 Kms	2	cum	696.19	
	ii, PPGI Sheets from 50 Kms	0.325	mt	514.39	
	iii. Cement from 20 Kms	0.8	mt	368.64	
	iii. Sand & Agg./ Soling Stones from 50 Kms	5.28	mt	630.26	
	Part B				
10	Providing wood work in frames of doors, windows. Clerestory windows and other frames, wrought framed and fixed in position by using of popular wood.	62.73	cft	RTQ	
11	Providing and fixing of windows of size 3'.6"x4'.0" along with glazed shutters/ wire guaze shutters of 2 nd class kail wood with required fitting items including cutting the walls and making good and fixed up in position complete job	2	no	RTQ	
Total cost of bid (to be quoted in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: IConstruction of PPGI sheets shed for accommodation of Telecommunication Department adjoining to Metrological Tower at Nunwan Camp.

S.No: 04

Adv. Amount: Rs. 1.62 lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	II	III	IV	V	VI
1	Providing wood work in frames of doors, windows. Clerestory windows and other frames, wrought framed and fixed in position by using of budloo / fir wood.	1.49	cum	60102.8	
2	Providing and fixing precoated galvanized iron profile sheets (size,shape and pitch of corrugation as approved by Engineer-in-charge) 0.50mm+/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240 mpa steel grade 5-7 microns epoxy primer on both sides of the sheet & polyester top coat 15-18 microns.. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal or with polymer coated J orL hooks bolts and nuts 8mm diameter with bitumen and G.I limpet complete upto pitch in horizontal/ vertical curved surface excluding the cost of purlins, rafters and trusses and including cutting to size and shap wherever required.	96.65	sqm	626.25	
3	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. With ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. 35 mm thick door including aldrops, tower bolts etc, complete, Size 7 FT X 3 FT	1.95	sqm	3187.85	
4	Carriage of material by mechanical transport from Anantnag to Nunwan avg. 50 Kms lead, including cost of loading and unloading.				
	wood	1.64	cum	696.19	
	PPGI Sheets	0.459	mt	541.39	
	Part B				
11	Providing and fixing of windows of size 3'.6"x4'.0" along with glazed shutters/ wire guaze shutters of 2 nd class kail wood with required fitting items including cutting the walls and making good and fixed up in position complete job	1	no	RTQ	
	Total cost of bid (to be quoted in figures and words)				

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Modification of Administrative huts 02 Nos. (Hut A1 & Hut A3) by way of providing of Teak wood wall lining/ Paneling with proper portioning to Huts at Nunwan Camp for use the Huts during Yatra-2022.

S.No: 05

Adv. Amount: Rs. 3.43 lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	II	III	IV	V	VI
1	Providing wood work in frames of false ceiling, partition etc sawn and fixed up in position (walls, ceiling & partition) a.Frame work for walls	1.5	cum	60102.8	
2	Providing and fixing of wooden moulded corner beeding of triangular shape to the junction of panelling; 2nd class kail wood (50x50mm)	8	mtr	249.35	
3	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. With ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. 35 mm thick door including aldrops, tower bolts etc, complete, Size 7 FT X 3 FT = 5 nos	9.75	sqm	3187.85	
4	Supply and fixing of curtain rods 1.25mm thick chromic pattern brass plate with two chronic plated brackets and side decorative caps etc complete job.	17	mtr	379.25	
5	Carriage of material from Anantnag to Nunwan Camp (50 km lead) including loading and unloading and carriage upto site of work. Wood , plywood, doors etc	2.89	cum	696.19	
	Part B				
6	Providing and fixing 4mm thick ply wood one side decorative veneered confirming to ISI specification for plain lining/ cladding (decorative veneer facing of approved manufacture Walls, Partition & Ceiling.	223.04	sqm	RTQ	
	Total cost of bid (to be quoted in figures and words)				

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Construction of scanning cabin / frisking and counting shed 01 No. (Wooden frame with PPGI sheet covering) at entry point at Lower Camp Sheshnag including dismantling after Yatra with proper stacking at SASB store.

S.No: 06

Adv. Amount: Rs. 1.39 lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	i	III	IV	V	VI
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth, lead upto 50 meter and lift upto 1.5m, as directed by Engineer-in-Charge. All kinds of soil:	27.88	sqm	83.45	
2	Excavating holes upto 0.10 cum, including getting out the excavated soil, then returning the soil as deposited in layers not exceeding 20 cm in depth, including consolidating and deposited layer by ramming watering etc., disposing of surplus excavated soil as directed with in a lead of 50 mm and lift upto 1.5 m.	10	no	26.55	
3	Providing and fixing of PPGI sheet covering 0.50 mm thick for sides and roofing fixed with necessary screws	63.19	sqm	626.25	
4	Carriage of material from Anantnag to Nunwan Camp (60 km lead) including loading and unloading and carriage upto site of work. Wood , plywood, doors etc				
	i. Timber / wood	1	cum	794.99	
	ii. PPGI Sheets etc	0.3	mtr	618.19	
5	Dismantling of shed after conclusion of yatra with stacking of material at store.	63.19	sqm	113.9	
	Part B				
6	Providing wood work in frames of doors, windows. Clerestory windows and other frames, wrought framed and fixed in position by using of popular wood.	37	cft	RTQ	
7	Carriage of material by head load from Chandanwari to Sheshnag by pithoos.	43	pithos	RTQ	
	Total cost of bid (to be quoted in figures and words)				

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Construction of PPGI shed (wooden frame with PPGI sheet covering) for Yatra counting / frisking of Yatries at Exit gate Sheshnag Camp.

S.No: 07

Adv. Amount: Rs. 1.39 lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	i	III	IV	V	VI
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth, lead upto 50 meter and lift upto 1.5m, as directed by Engineer-in-Charge. All kinds of soil:	27.88	sqm	83.45	
2	Excavating holes upto 0.10 cum, including getting out the excavated soil, then returning the soil as deposited in layers not exceeding 20 cm in depth, including consolidating and deposited layer by ramming watering etc., disposing of surplus excavated soil as directed with in a lead of 50 mm and lift upto 1.5 m.	10	no	26.55	
3	Providing and fixing of PPGI sheet covering 0.50 mm thick for sides and roofing fixed with necessary screws	63.19	sqm	626.25	
4	Carriage of material from Anantnag to Nunwan Camp (60 km lead) including loading and unloading and carriage upto site of work. Wood , plywood, doors etc				
	i. Timber / wood	1	cum	794.99	
	ii. PPGI Sheets etc	0.3	mtr	618.19	
5	Dismantling of shed after conclusion of yatra with stacking of material at store.	63.19	sqm	113.9	
	Part B				
6	Providing wood work in frames of doors, windows. Clerestory windows and other frames, wrought framed and fixed in position by using of popular wood.	37	cft	RTQ	
7	Carriage of material by head load from Chandanwari to Sheshnag by pithoos.	43	pithos	RTQ	
	Total cost of bid (to be quoted in figures and words)				

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Erection of PPGI Sheet Shed dismantlable for accommodation of Sadhu's at Sheshnag camp for yatra -2022.

S.No: 08

Adv. Amount: Rs. 2.78 lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	i	III	IV	V	VI
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth, lead upto 50 meter and lift upto 1.5m, as directed by Engineer-in-Charge. All kinds of soil:	92.94	sqm	83.45	
2	Excavating holes upto 0.10 cum, including getting out the excavated soil, then returning the soil as deposited in layers not exceeding 20 cm in depth, including consolidating and deposited layer by ramming watering etc., disposing of surplus excavated soil as directed with in a lead of 50 mm and lift upto 1.5 m.	20	no	26.55	
3	Providing and fixing pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %). Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 meter or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws or required fixtures, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.				
	ii. PPGI Sheets new procurement.	109.29	sqm	626.25	
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m. Filling for raising of platform. including its excavation from nearby pits.	13.59	cum	634.7	
5	Carriage of Cement by Mechanical Transport Avg. distance 60 Km				
	i. Timber / wood	2.08	cum	794.99	
	ii. PPGI Sheets etc	0.74	mtr	618.19	
6	Dismantling of shed after conclusion of yatra with stacking of material at appropriate site.	156.13	sqm	113.9	
	Part B				
7	Providing wood work in frames of doors, windows. Clerestory windows and other frames, wrought framed and fixed in position by using of popular wood.	73.49	cft	RTQ	
8	fixing of available CGI sheets to sadhu shed walls.	46.84	sqm	RTQ	
9	Carriage of material by head load from Chandanwari to Sheshnag for timber/ wood and PPGI Sheets by Pithoos.	78	pithus	RTQ	
	Total cost of bid (to be quoted in figures and words)				

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Construction of Soakage Pits for newly proposed toilet bases at Pissu Top, Zojibal and other required spots along enrout.

S.No: 09

Adv. Amount: Rs. 4.41 lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	i	III	IV	V	VI

1	Earth work in excavation by manual means in trenches for foundations, drains, pipes , cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed 2.8.1 All kinds of soil : (Lead upto 1 meter from cutting edge) 30% O.R and 70%(S.S)	125.61	cum	598.25	
2	Extra for Additional lift of 1.5 Mtr. and thereof.	62.6	cum	81.65	
3	Dry Random Rubber Masonry with hard stone by using Nallah Aggregate without bond stone.	73.36	cum	2355.95	
4	Back filling of trunch with available material.	16.68	cum	198.7	
5	Providing and laying cement concrete of specified grade in 1:2:4 mix (Slab of Pits)	4.47	cum	5877.45	
6	Reinforcement for RCC work including cutting, Bending straitening and placing in position and binding etc complete. 12mm&10mm	350	kg	79.25	
7	Centering and shuttering including strutting, propping etc. removal of frame work for foundations, footings, bases of columns etc. for mass concrete.	11.67	sqm	262.3	
8	Carriage of Cement by Mechanical Transport Avg. distance 36 Km	1.78	mt	433.67	
9	Carriage of material by head load from nearby source to works sites for sand and aggrigates avg distance 3 kms , and stones from 1 km				
	i. sand and aggrigates	6.03	cum	2527.18	
	ii. Stones	73.36	cum	1102.98	
	Part B				
9	Head load of cement and steel from chandanwari to working site	18	pony	RTQ	
Total cost of bid (to be quoted in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder



SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Up-gradation of holding capacity of yatries by way of improvements to additional area at c. block tent for piching of additional 200 no Tents to enhance the carrying capacity of 2000 Yatries at Sheshnag.

S.No: 10

Adv. Amount: Rs. 1.70 lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	i	III	IV	V	VI

1	Earth work in Surface excavation not exceeding 30cm on depth but excluding 1.5 Mtr. In width as well as 10 Sqm on plane, including disposal of excavated earth lead upto 50 mtr. and lift upto 1.5 mtr. or as directed in all kinds of soil.	2049	cum	83.45	
Total cost of bid (to be quoted in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder



SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Part A. Assembling/ installation of 08 no. wash basins (stainless steel) at Chandanwari and enroute from Chandanwari to Sheshnag with all carriage of material and dismantling after Yatra including their carriage upto safe storage site.

Part (B) Installation of Reverse Vending Machine Shed for Shredding of waste plastic bottles at Chandanwari Camp.

S.No: 11

Adv. Amount: Rs. 0.50 lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	i	III	IV	V	VI
	PART (A)				

1	Carriage of wash basins from storage site upto site of installation including; i. Assembling of S.S. wash basins with required nuts/bolts etc, ii. Fixing of GI pipe line inside the wash basin complete, iii. Fixing of required sanitary items i.e. bid cock, pvc connection and waste pipes complete. iv. Fixing of PVC pipes for disposal of water upto appropriate place.	430.5	Kg	RTQ	
2	Supply of pipes for disposal line 75mm dia fitting items				
	i. PVC pipe 75 mmdia	48	rm	89	
	ii. PVC Tee 75 mmdia	9	no	62	
	iii. PVC bend 75 mmdia	16	no	46	
	iv. Bid cock (PTMT) 15mmdia	12	no	127	
3	Carriage of material from Anantnag to Chandanwari including loading and unloading.	1	trip	RTQ	
4	Dismantling of wash basins from installation site including head load of material with packing and storing at site.	430.5	kg	RTQ	
5	Carriage of PVC pipes from Chandanwari to installation site including fitting items upto Sheshnag.	2	pithoo	RTQ	
	PART (B)				
1	Carriage of material from SASB Store to site of installation site including loading and unloading of material	1	trip	RTQ	
2	Hire charges of Crane/ JCB for carrying of Machine from storage site to installation site including placing of machine at appropriate position	5	hour	RTQ	
3	Engagement of electrician for providing of electricity to Shredding machine	2	eletrition	980	
4	Installation of shed for reverse vending machine pre Yatra and its dismantling post yatra by way of engaging skilled labours Blacksmith pre yatra.	5	no	980	
5	Back carriage of machine after conclusion of Yatra including safe storage.04 hours of Crane /JCB	4	hour	RTQ	
6	Back carriage of shed after conclusion of yatra with safe storage of material	1	trip	RTQ	
	Total cost of bid (to be quoted in figures and words)				

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder



SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Covering of SASB area (Administrative Block) by way of providing available CGI sheets/
Panels for fencing at Sheshnag.

S.No: 12

Adv. Amount: Rs. 0.30 lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	i	III	IV	V	VI
1	Fixing of CGI Sheet panels as fencing wall in front of administrative block of SASB at Sheshnag Camp including repairs to frame posts of fencing wall with all leads and lifts of material all complete including dismantling from existing Huts.	132.44	sqm	RTQ	

2	Dismantling of material utilized after conclusion of yatra with refixing as safety panels to pre-fabricated huts all complete.	132.44	sqm	RTQ	
Total cost of bid (to be quoted in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Covering of toilet area behind Langars at Chandanwari with Agronet on Steel posts.

S.No: 13

Adv. Amount: Rs. 1.40 lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	i	III	IV	V	VI

1	Excavating holes upto 0.10 cum, including getting out the excavated soil, then returning the soil as deposited in layers not exceeding 20 cm in depth, including consolidating and deposited layer by ramming watering etc., disposing of surplus excavated soil as directed with in a lead of 50 mm and lift upto 1.5 m.	100	No	26.55	
2	Supplying at site Angle iron post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia. etc. complete.	853.65	kgs	88.5	
3	Supply and fixing of Agronet Jal for covering of toilet and bath areas for proper privacy of yatris while using the toilets .	6000	sft	RTQ	
4	Dismantling of Agronet covering / fencing from designated spots after conclusion of yatra including carriage of material upto store with proper stacking of material etc. complete job.	1	job	RTQ	
Total cost of bid (to be quoted in figures and words)					
Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.					

DGM(Works)
Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Renovation of Pucca Toilets (20 Nos.) with repair to sewage disposal line thereof at Nunwan base camp for Yatra-2022.

S.No: 14

Adv. Amount: Rs. 0.72 Lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	ii	III	IV	V	VI
1	Repair the damaged roofing to toilet blocks (02 cluster of 10 no. pucca Toilets) complete job.	20	Sqm	RTQ	

2	Providing and fixing CGI Sheets for roofing of toilets fixed with J & L Hooks with required Bitumen, Limpet washers Complete (0.50mm thick).	25	Sqm	830.25	
3	Removing white or colour wash by scrapping and sand parping and preparing the surface smooth including repairs to scratches etc. complete. For 20 No. Toilets.	150.92	sqm	13.2	
4	Distemping with 1 st quality acrylic/ oil bound washable distemper (ready-made) having VOC content less than 50 grams/litre of approved manufacture and of required shade and colour complete as per manufactures, specifications, one or more coats on old work.	249.81	Sqm	46.7	
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade, one or more coats on old work.	50	sft	52.04	
6	Hire charges of Welding set, Gen Set, Welding rods and POL etc. for Repair the doors of Toilets and fixing of all fittings, fixtures and repairs to dents etc. complete job. 02 days	2	day	RTQ	
7	Supply of MS fittings and fixtures for doors of Toilets				
	i. Oxidised MS sliding Door bolt 250x16mm	20	no	96	
	ii. MS Butt hinges 100x58x1.10mm	30	no	9.5	
	iii. 125mm Oxidised M. Steel Handles	20	no	25	
	iv. PVC Pee trap 110mm dia	20	no	RTQ	
	v. PVC Pipe 110mm dia	20	mtr	236.8	
8	Dismantling W.C. Pan of all sizes including disposal of dismantled material and malba all complete as per directions	6	no	87.15	
9	Demolishing cement concrete manually/by mechanical means incl. disposal of material within 50 mtrs. Lead as per directions. In 1:3:6 Or richer mix. For 6 No.Toilets	0.85	cum	1569.2	
10	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings	6	no	1449.35	
11	Carriage of material by M. Transport	1	trip	RTQ	
	Total				
Total cost of bid (to be quoted in figures and words)					
Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.					

DGM(Works)
Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Construction of sub-structure for the Residential Hut for service providers for issuance of Smart Card (tracking) to yatrics for Shri Amarnathji yatra at Chandanwari.

S.No: 15

Adv. Amount: Rs.0.69 Lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	ii	III	IV	V	VI

1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth lead upto 50 metres and lift upto 1.5m, disposed earth to be levelled and neatly dressed in All kinds of soil:	30.75	Sqm	83.45
2	Earth work in excavation by manual means in trenches for foundations, drains, pipes , cablesetc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed 2.8.1 All kinds of soil : (Lead upto 1 meter from cutting edge).	1.86	Sqm	436
3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering . All work upto plinth level with:			
	Mud mate : Foundation/plinth 1:4:8	2.72	Cum	4419.85
	Column foundation in (1:2:4)	0.8	cum	5877.45
	D.P.C 50mm thick in (1:2:4)	9.63	Sqm	372.85
	Concrete in 1:3:6. Mix,	0.23	cum	4943.4
5	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded crushed stone aggregate)50 mm thick finished with a floating coat of neat cement, including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete.	25.41	Sqm	505
6	Providing and fixing of glass strips to flooring40xmm	30	Rm	68.25
7	Random rubble masonry with hard stone in foundation and plinth including levellingup with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate20 mm nominal size) upto plinth level and curing complete with :Cement mortar 1:6 (1 cement: 6 coarse sand).	2.51	cum	4435.25
7	Centring and shuttering including strutting, propping etc and removal of form for:Foundations, footings, bases of columns etc for mass concrete.	5.04	Sqm	262.3
8	Filling to plinth with available excavated soil including ramming watering etc for complete consolidation.	3.17	cum	198.7
9	Providing and fixing of sanitary items to attached toilet/bath of hut.			
	Providing and fixing white vitreous china pedestal type (European type/wash down type) water closet pan.	1	Each	2217.5
	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS: 7231 with all fitting and fixtures complete. 10 liter capacity –white	1	Each	976.05
	Providing and fixing PTMT angle stop cock 15 mm nominal bore. Weighing not less than 85 gms.	2	Each	230.5

	Providing and fixing slid plastic seat with lid for pedestal type W.C. pa complete. White solid plastic seat with lid.	1	Each	776.55
	Providing and fixing 8 mm dia C.P./S.S. jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer –in-charge.	1	Each	328.35
	Providing and fixing brass bib cock of approved quality. 5 mm nominal bore.	2	Each	318.85
	Providing and fixing G.I pipes complete with G.I. fittings excluding trenching and refilling etc (External work) 15 mm dia nominal bore. =12 Mtr (Medium)	12	Rm	163.55
	PVC pipe 110 mm dia.	3	Mtr	177
	P.V.C. Bends 110 mm dia	3	No	92
	Providing and fixing of plasticized PVC connection pipe with brass unions 45 cm length.	2	No	87.9
	Providing and fixing G.I Union in G.I pipe including cutting and threading the pipe and make long screws etc complete (new work) 15 mm nominal bore.	1	No	259.5
10	Carriage of material through mechanical transport			
	Cement from 36 km including loading & unloading.	1.65	mt	433.87
	Sand aggregate from average 65 km including loading & unloading.	8.38	cum	738.62
	Stones from average 10 km lead including loading & unloading.	2.51	cum	287.32
	Sanitary items From Anantnag to Chandanwari	1	trip	RTQ
Total cost of bid (to be quoted in figures and words)				

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Construction of sub-structure for the Residential Hut for service providers for issuance of smart card (tracking) to yatrics for Shri Amarnathji yatra at Sheshnag

S.No: 16

Adv. Amount: Rs.1.00 Lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	ii	III	IV	V	VI

1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth lead upto 50 metres and lift upto 1.5m, disposed earth to be levelled and neatly dressed in All kinds of soil:	30.75	Sqm	83.45	
2	Earth work in excavation by manual means in trenches for foundations, drains, pipes , cable etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed 2.8.1 All kinds of soil : (Lead upto 1 meter from cutting edge).	1.86	Sqm	436	
3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering . All work upto plinth level with:				
	Mud mate : Foundation/plinth 1:4:8	2.72	Cum	4419.85	
	Column foundation in (1:2:4)	0.8	cum	5877.45	
	D.P.C 50mm thick in (1:2:4)	9.63	Sqm	372.85	
5	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded crushed stone aggregate)50 mm thick finished with a floating coat of neat cement, including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete.	25.41	Sqm	505	
7	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level and curing complete with :Cement mortar 1:6 (1 cement: 6 coarse sand).	2.51	cum	4435.25	
7	Centring and shuttering including strutting, propping etc and removal of form for: Foundations, footings, bases of columns etc for mass concrete.	5.04	Sqm	262.3	
8	Filling to plinth with available excavated soil including ramming watering etc for complete consolidation.	3.17	cum	198.7	
10	Carriage of material through mechanical transport Cement from 36 km including loading & unloading.	1.65	mt	433.87	
11	Sand aggregate from average 3 km including loading & unloading.	8.38	cum	2527.18	
12	Stones from average 1 km lead including loading & unloading.	2.51	cum	1102.98	
	Part B				
13	head load of material from chandanwari to sheshnag	16	pony	RTQ	
	Total cost of bid (to be quoted in figures and words)				

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Repairs, Painting, Writing and Numbering of Toilets Sheshnag Camp for Yatra-2022

S.No: 17

Adv. Amount: Rs.1.85 Lakh

S. No.	Particulars of Items	Quality	Unit	Rate as per SSR-2020	Rate to be quoted by the bidder (in %age above or Below)
I	ii	III	IV	V	VI

1	Removing colour or white wash by way of Scraping and sand papering to prepare surface smooth for painting.	159	Sqm	13.2	
2	Applying priming coat with ready mixed red oxide zinc-chromate primer of approved Brand and Manufacture on steel work	159	Sqm	52.75	
3	Painting with synthetic enamel paint of approved brand and Manufacture of required colour and shade, one or more coats on old work and new work				
	A= Old work	1437	sqm	80.1	
	B = New work	159	sqm	121.95	
4	Re-Lettering with Black Japan Paint of approved brand and manufacture;	3000	cm	2.9	
5	Repair to prefab Toilets/baths by way of denting, Patch repair etc. complete.	100	No	RTQ	
6	carriage of material both mech. And head load up to sheshnag camp	1	job	RTQ	
Total cost of bid (to be quoted in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

DGM(Works)
Pahalgam

Signature of Bidder

