

**Corrigendum to NIT No. SASB/NIT/Works/818/2016/05 dated 08.01.2016**

Please read following amendments in the Schedule B of Financial Bid:

Provided in the Tender Document	Read as
<b>Schedule B- (Financial Bid)"B-a" item 1 (i) page no. 37</b>	
<b>Base Frame Structure</b>	
<b>Zinc coated (Non Rusting) nuts and bolts:</b>	
12x40 mm = 3000 nos. 10x75 mm = 6000 nos. (514 kgs)	12x40mm = 12 nos. 10x50mm = 08 nos. 10x65mm = 25 nos. 10x65mm = 06 nos. (CSK) 6x50mm = <u>06 nos.</u> <b>= 57 nos.</b> = 2.8 kg's (for one Toilet) for 200 Toilets European Type = <b>560 kgs</b>
<b>Schedule B- (Financial Bid)"B-b" item 1 (i) page no. 39</b>	
<b>Base Frame Structure</b>	
<b>Zinc coated (Non Rusting) nuts and bolts:</b>	
12x40mm = 3375 nos. 10x75mm = 6750 nos. (578 kgs)	Zinc coated (Non Rusting) nuts and bolts 12x40mm = 12 nos. 10x50mm = 08 nos. 10x65mm = 25 nos. 10x65mm = 06 nos. (CSK) 6x50mm = <u>06 nos.</u> <b>= 57 nos.</b> = 2.8 kg's (for one Toilet) for 225 Toilets Indian Type = <b>630 kgs</b>
<b>Schedule B- (Financial Bid)"B-c" item 1 (i) page no. 41</b>	
<b>Base Frame Structure</b>	
<b>Zinc coated (Non Rusting) nuts and bolts:</b>	
12x40mm = 2100 nos. 10x75mm = 4200 nos. (360 kgs)	12x40mm = 12 nos. 10x50mm = 08 nos. 10x65mm = 25 nos. 10x65mm = 06 nos. (CSK) 6x50mm = <u>06 nos.</u> <b>= 57 nos.</b> = 2.8 kg's (for one Bath) for 140 Baths = <b>392 kgs</b>
<b>Schedule B- (Financial Bid)"B-a" item 1 (i) page no. 37</b>	
Providing and fixing of POP rivet 5x20mm = 30000 nos. Self drilling screw 20mm long = 4000 nos.	Deleted
<b>Schedule B- (Financial Bid)"B-b" item 1 (i) page no. 39</b>	
Providing and fixing of POP rivet 5x20mm = 33750 nos. Self drilling screw 20mm long = 4500 nos.	Deleted
<b>Schedule B- (Financial Bid)"B-c" item 1 (i) page no. 41</b>	
Providing and fixing of POP rivet 5x20mm = 21000 nos. Self drilling screw 20mm long = 2800 nos.	Deleted
<b>Schedule B (Financial Bid)"B-a, B-b and B-c" item 3 and B-c item 4":</b>	
Providing and fixing Pre-coated coloured sheet galvanized iron PPGI – 0.60mm thick for side wall panels and roofing with required <b>self driven screws</b> not more than 300 mm spacing".	Providing and fixing Pre-coated corrugated coloured sheet galvanized iron PPGI – 0.60mm thick for side wall panels and roofing with required no. of <b>self driven screws with POP rivets</b> (5x20mm) not more than 300 mm spacing. For Schedule B (Financial Bid)"B-a, B-b and B-c" item 3
<b>Schedule B (Financial Bid)" item 3 of B-a, B-b and B-c:</b>	
Providing and fixing of <b>Stainless Steel Grating Chromium Plated</b> for floor.	Providing and fixing of <b>PVC Waste Coupling</b> at floor level 31mm (heavy duty).

**Note: Consequently the Job Description at S. No. 2 Page 8-10 is amended accordingly.**

Sd/-

**DGM (B)**

SASB/NIT/W/818/2016/09

Dated 28.01.2016

Sd/-

**DGM (P)**

Sd/-

**GM (Works)**



## **SHRI AMARNATHJI SHRINE BOARD**

Chaitanya Ashram, Talab Tillo, Jammu (Nov-April)

Tele: 0191-2555662, Telefax: 0191-2503399

### **Corrigendum to NIT No.**

#### **SASB/NIT/Works/818/2016/05 dated 08.01.2016**

The date of receipt of tenders has been extended up to 16.02.2016 (1400 hours) instead of 09.02.2016 and sale of tender documents is also extended up to 13.02.2016 (1700 hours). Technical Bid shall be opened on 16.02.2016 at 1500 hours.

Also refer corrigendum no. SASB/NIT/W/818/2016/09 dated 28.01.2016 for amendment to Schedule B of Financial Bid on our website: [www.shriamarnathjishrine.com](http://www.shriamarnathjishrine.com).

No: SASB/NIT/W/818/2016/10

Sd/-

Dated 28 .01.2016

**Additional Chief Executive Officer**