

**CIVIL WORKS ALONG BALTAL AXIS FOR YATRA 2016**

**DETAILED NOTICE INVITING TENDER (DNIT)**

(issued under no. \_\_\_\_\_ dated \_\_\_\_\_)

<b>S. NO.</b>	<b>CONTENT</b>	<b>PAGE (S)</b>
1	Notice Inviting Tender (NIT) for advertisement	2-4
2	Eligibility criteria	5
3	Documents establishing Bidder's eligibility	5
4	Instructions to Bidders	5-8
5	Scope of work	8-9
6	Terms and Conditions of Contract	9-12
7	Schedule – A (Technical Bid)	13-14
8	Schedule – B (Financial Bid)	15



## SHRI AMARNATHJI SHRINE BOARD

Chaitanya Ashram, Talab Tillo, Jammu (Nov-April)

Tele: 0191-2555662. Telefax: 0191-2503399

### NOTICE INVITING TENDER

#### CIVIL WORKS ALONG BALTAL AXIS FOR YATRA 2016

On behalf of Chairman, Shri Amarnathji Shrine Board, sealed tenders in two-bid format, affixed with Rs.6/- revenue stamps, are invited from experienced and financially sound registered **PWD Contractors** whose Registration Certificates are valid for Financial Year 2016 - 2017, for the execution of various Works mentioned below, at the Baltal Camp. These bids shall be received in the office of General Manager (Works), Shri Amarnathji Shrine Board, at Chaitanya Ashram, Talab Tillo, Jammu, on or before **22.03.2016** up to 1400 hours

S. No.	Name of work	Approx. Cost (in Lac)	Earnest Money Deposit (in Rs)	Class of Contractor	Time of Completion	Cost of bid document
1	Assembling of Toilet/ Baths (500 nos.) and fixing of P.V.C pipes with minor repairs (welding and denting) including aligning and clearance of choked sewer line and cost of dismantling / stacking after culmination of Yatra – 2016 at Baltal Camp.	4.80	9600/-	D	25 Days	500/-
2	Assembling of Toilet/ Baths (395 nos.) with minor repairs (welding and denting), fixing of P.V.C pipes, cleaning/ excavation of earthen disposal pits including cost of dismantling/stacking of Toilets/Baths at enroute Ranga morh to Domel and Neelgrath Helipad area	6.30	12700/-	D	25 Days	500/-
3	Construction of two no. sheds (size: 20'x12') for Food Supply Department, one no. Shed (size: 20'x12') for Labour Department, one no. Medical Shed (size: 12'x12') at Domail for Medical Deptt., one no. shed for Kitchen of PHE Department (size: 15'x12'), one no. shed for HP Gas (size: 20'x12'), one no. Shed for PDD (size: 12'x12'), two no. frisking shed (size: 10'x30') and one no. (20'x40') for cloak room , 03 no. Gas Store ( 10'x30') for storage of HP Gas for langars including cost of its dismantling/stacking after culmination of Yatra at Baltal.	5.20	10500/-	D	25 Days	500/-
4	Improvement to existing sewer line of toilet/ baths by way of providing additional 250 mm dia RCC Spun pipe length 370 meter at Baltal. (RCC spun pipe to be supplied departmently)..	3.00	6000/-	D	15 Days	Rs 500/-
5	Laying of sub distribution GI pipe line 15 mm dia for water supply at enroute Ranga Morh to Domel and in Langar store area including cost of its dismantling/stacking after culmination of Yatra at SASB store.	2.30	4600/-	D	25 Days	Rs 500/-
6	Plantation of Reed plant in Oxidation Chambers of STP at Baltal.	0.60	1200/-	D	10 Days	Rs 200/-
7	Turfing of STP and Grease Trap area at Baltal.	1.18	2400/-	D	15 Days	Rs 300/-
8	Laying of Precast cement concrete tile on foot path from Grease Trap to Prefab toilet/ Baths on back side of Langar No. 1-6 via STP at Baltal.	0.80	1600/-	D	15 Days	Rs 200/-
9	Providing of fire gaps and paths in between tent- age area by way of excavation of drain, earth work filling and laying of RBM at Baltal.	1.90	3800/-	D	20 Days	Rs 400/-
10	Laying of precast cement concrete tile flooring from Main Road to Gate No. 2 via frisking at Baltal.	0.80	1600/-	D	15 Days	Rs 200/-
11	Clearance/ Improvement of choked drain inside Baltal Camp and Helipad area including its reconstruction with dry random rubble masonry stone at Baltal Camp. Approx. Length 1500 mtrs.	1.60	3200/-	D	15 Days	Rs 400/-
12	Erection of CGI sheet walling for partitioning of STP and Langars, providing and fixing of agro-net partition in front of ladies toilet/bath including cost of its dismantling /stacking after culmination of yatra at Baltal Base Camp.	0.75	1500/-	D	10 Days	Rs 200/-

13	Providing and Fixing of G.I. Pipe Railing 50mm dia at frisking point at Baltal.	0.90	1800/-	D	10 Days	Rs 200/-
14	Repair/ Re-erection of barbed wire fencing, fencing of old Helipad area ,Medical Camp at Domel , damaged fencing to STP area and Grease Trap including cost of its dismantling/stacking after culmination of Yatra at Baltal Camp.	3.40	6800/-	D	20 Days	Rs 500/-
15	Mounting of water storage tank on existing stages, water supply fitting, fixing of 02 nos. motor pump and fixing of chain link fencing including cost of its dismantling/stacking after culmination of Yatra at Neelgrath.	0.80	1600/-	D	10 Days	Rs 200/-
16	Construction of (02 no.) fuel depot including cost of its dismantling/stacking after culmination of Yatra at Neelgrath.	0.35	700/-	D	10 days	Rs 100/-
17	Painting of Prefabricated huts (40 nos.) at Baltal.	1.40	2800/-	D	15 Days	Rs 300/-
18	Painting of Prefabricated toilet/ baths at Baltal Base Camp, Rangamohr to Domel including Neelgrath Helipad (300 nos.).	3.00	6000/-	D	15 Days	Rs 500/-
19	Re-roofing and painting of Hangar including Dismantling /stacking of roofing after the culmination of yatra at Baltal.	2.40	4800/-	D	20 Days	Rs 500/-
20	Re-roofing/ renovation and painting/ white washing of pacca toilet including its cost of dismantling after culmination of Yatra at Baltal.	2.00	4000/-	D	15 Days	Rs 400/-
21	Laying of sub distribution pipe line 15 mm dia for water supply in Baltal Camp and old Helipad area including cost of its dismantling/stacking after culmination of Yatra at Baltal Camp.	1.75	3500/-	D	25 Days	Rs 400/-
22	Assembling of Toilet/ Baths (160 nos.) including fixing of P.V.C. pipes with minor repairs and cleaning/ excavation of earthen disposal pits including cost of dismantling/ stacking of toilets/ baths after conclusion of Yatra at enroute Domel to Holy Cave.	3.20	6400/-	D	20 Days	Rs 500/-
23	Assembling of Toilet/ Baths (259 nos.) including fixing of P.V.C. pipes with minor repairs and cleaning / excavation of earthen disposal pits including cost of dismantling/ stacking of toilets/ baths after conclusion of Yatra at Holy Cave.	4.90	9800/-	D	25 Days	Rs 500/-
24	Assembling of prefabricated huts (09 nos.) with minor repairs including cost of its dismantling /stacking after conclusion of Yatra at Holy Cave.	5.40	10800/-	D	25 Days	Rs 500/-
25	Improvement to CGI sheet Store at Brarimarg.	0.60	1200/-	D	10 Days	Rs 200/-
26	Construction of BSNL staff shed, labour shed , SASB staff shed and store for SASB material including cost of its dismantling /stacking after conclusion of Yatra at Holy Cave.	0.84	1700/-	D	10 Days	Rs 200/-
27	Construction of Shoe-rack shed (size: 14'x10'), Frisking shed (size 8'x8') and cloak room shed including cost of its dismantling /stacking after conclusion of Yatra at Holy Cave.	0.75	1500/-	D	10 Days	Rs 200/-
28	Construction of pandal ( 50'x35' including cost of its dismantling /stacking after conclusion of Yatra at Holy Cave.	1.50	3000/-	D	10 Days	Rs 300/-
29	Erection of Barbed wire fencing to Medical Camps (05 nos.) of (size 25'x50') including cost of its dismantling and stacking after culmination of Yatra at en-route Domel to Brarimarg.	1.37	2750/-	D	15 Days	Rs 300/-
30	Installation of Sign Boards and informatory Boards including cost of its dismantling, carriage and stacking after culmination of Yatra at enroute Domel to Holy Cave and Sangam to Panjtarni.	0.60	1200/-	D	10 Days	Rs 200/-
31	Assembling of railing along the stairs, around the Nandi point and erection of entrance gate including cost of its dismantling and proper stacking after culmination of Yatra at Holy Cave.	1.30	2600/-	D	15 Days	Rs 300/-
32	Assembling of (03 no.) Wooden foot bridges including cost of its dismantling / proper stacking after culmination of Yatra at Kali Mata Track.	0.80	1600/-	D	10 Days	Rs 200/-

33	Fixing and painting of railing post and railing pipes including fixing of barriers, laying and painting of milestone including cost of its dismantling and stacking after culmination of Yatra at Kali Mata Track	3.25	6500/-	D	20 Days	Rs 500/-
34	Painting of Prefabricated toilet/ baths at enroute Domel to Holy Cave.	0.95	1900/-	D	10 Days	Rs 200/-
35	Painting of Prefabricated toilet/ baths at Holy Cave (100 nos.).	1.50	3000/-	D	15 Days	Rs 300/-
36	Painting and Repair of grill and counting hall at Holy Cave.	0.30	600/-	D	08 Days	Rs 100/-
37	Clearance of snow (frosted snow) from stairs, Helipad and Track from Helipad to upstairs at Holy Cave.	3.40	6800/-	D	20 days	Rs 500/-
38	Clearance of snow (frosted snow) from Kali Mata Track.	1.55	3100/-	D	15 days	Rs 400/-

2. Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu from 9.30 AM to 5.00 PM, on any working day (Monday-Saturday) up to **19.03.2016** on payment of cost of document in cash or in the shape of Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), Jammu.
3. The Tender, duly completed, along with Earnest Money Deposit in the form of CDR in favour of Chief Accounts Officer, Shri Amarnathji Shrine Board payable at Jammu / Srinagar, must reach latest by **1400 hours on 22.03.2016**. The bidders, in their own interest, are advised to deliver the bids personally in the office of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu. Alternatively, they may send the same through courier/ registered post. The Board will not be responsible for any delay, wrong delivery or non-delivery of the bids due to any reason.
4. The Technical bid shall be opened at **10 am on 24.03.2016** in the office of General Manager (Works), (at Jammu Office; address mentioned above) in presence of the Agencies/ Bidders who may wish to be present on the occasion.
5. Not more than two Bid documents shall be issued to a single bidder.
6. In case the last date of receipt of Bid happens to be a holiday, the Bid shall be received on the next working day up to 1400 hours.
7. The successful bidder is bound to enter into an Agreement with General Manager (Works) SASB, within fifteen days from the date of the issue of Letter of Allotment of Work.

**No: SASB/NIT/2016/ 848/ 12**  
**Dated:29.02. 2016**

**sd/-**  
**General Manager (works)**  
Shri Amarnathji Shrine Board

## **ELIGIBILITY CRITERIA**

The Bidder must be a Contractor (registered with PWD J&K) and must fulfil all the following eligibility requirements concurrently to technically qualify for this bidding process;

- 2.1 The Bidder must possess at-least three year's experience (experience from Calendar Year 2011 to 2015 shall only be considered) in the field of Civil Construction in hilly region.
- 2.2 The Bidder should possess the experience of completion of at least 03 works of similar nature to those mentioned in the DNIT in High altitude area of which at least one work should be of cost not less than fifty percent of the amount of the tendered work with SASB.
- 2.3 The Bidder should have an average Annual Turnover of at least Rs. 3.00 lakh during at least one of the financial year from Financial Year 2012-13 to Financial Year 2014-15.
- 2.4 The Bidder should not have been blacklisted on an earlier occasion by any of the State Government Organizations, State Autonomous Bodies or Local Bodies/ Municipalities.

## **III DOCUMENTS ESTABLISHING BIDDER'S ELIGIBILITY**

The Bidder must submit the following documents:

- 3.1 Registration Certificate authenticating the same.
- 3.2 Certified copies of Annual Turnover from Bank.
- 3.3 Certified documents like Letter of Award/ Offer, Work Order, Contract Agreement, Certificate of Completion etc. indicating experience and execution of similar works, for fulfilling the eligibility criteria.
- 3.4 Certified copy of PAN Card.
- 3.5 Certified copy of TIN Registration Certificate.
- 3.6 General Profile of the Bidder
- 3.7 An affidavit by the Bidder, Stamp Paper of Rs. 10, stating that all information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against him. If any information is found to be incorrect at any time, the Security Deposit shall stand forfeited.

## **IV. INSTRUCTIONS TO BIDDERS**

- 4.1 Detailed NIT (DNIT) can be obtained from the office of Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu, from 9.30 AM to 5.00 PM on any working day (Monday-Saturday) till 19.03.2016 on payment of cost of Tender Document prescribed against each work in the DNIT in cash or in the shape of a Demand Draft

drawn in favour of Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), J&K.

- 4.2 The Bidders are required to submit the bid in two parts – **Technical** and **Financial** - strictly as per format given in **Schedule A** and **Schedule B** of the DNIT along with requisite supporting documents. The two parts of the **Bid** should be submitted in two separately sealed envelopes superscribed “**Technical Bid for the work of \_\_\_\_\_ Yatra 2016**” and “**Financial Bid for the work of \_\_\_\_\_ Yatra 2016**”. Both the sealed envelopes should be put in a third envelop, sealed and superscribed “**Tender for the work of \_\_\_\_\_ (Yatra 2016)**” **mentioning NIT No. & date**. The bids, as are not submitted as per format prescribed in **Schedule A and B** are liable to be rejected.
- 4.3 The Bids, duly completed, along with an Earnest Money Deposit (EMD) of amount prescribed in the DNIT ( against each Work) only in the form of CDR/ Demand Draft drawn in favour of Financial Advisor / Chief Accounts Officer “Shri Amarnathji Shrine Board” payable at Jammu, must be dropped in the Tender Box kept in the office chamber of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu, or sent by Registered Post/ Courier to FA/ Chief Accounts Officer at the aforesaid address, so as to reach by **1400 hours 22.03.2016 latest**. Bids received after the aforesaid date and time will not be considered. The Shrine Board shall not be responsible for any delay/ loss of documents or correspondence sent by courier/ post. The technical Bids shall be opened at **10 a.m. on 24.03.2016** in the office of General Manager (Works), (at Jammu office) in presence of the Contractors/ Bidders.  
In case last date of receipt of bids happens to be a holiday, the bids shall be received on the next working day up to 1400 hours and shall be opened on the same day at 1500 hours.
- 4.4 Bids not accompanied by EMD shall be summarily rejected. The EMD and cost of DNIT should be placed inside the envelope containing the Technical Bid. The EMD shall be forfeited if the Bidder withdraws his bid during Bid Validity Period.
- 4.5 It would be deemed that by submitting the Bid, the Bidder has made complete examination of the DNIT, received all information requested from SASB and made complete examination of the various aspects required for undertaking the stated works.
- 4.6 Each Bidder can submit only one Bid in response to a work in the DNIT. Any Bidder who submits more than one Bid shall be disqualified.
- 4.8 The Bidder is expected to examine all Instructions, Schedules, Formats, Terms and Conditions, Scope of Work mentioned in the DNIT. Failure to furnish all information required in the Tender Document or submission of Bid not substantially responsive to the DNIT in every respect will be at Bidder’s risk and may result in the rejection of the bid.
- 4.9 All entries in the Technical/ Financial Bids should be legible and should be free from corrections/ erasures. The corrections, if any, must be attested by the Bidder. Amounts shall be indicated in words as well as in figures. Where there is a difference between amount mentioned in

figures and words, the amount quoted in words shall be taken as authentic.

- 4.10 The Bidder must satisfy himself that it fulfils all the prescribed eligibility conditions to avoid rejection of his Bid.
- 4.11 Each paper of the Bid document shall be completed in all respects, page numbered, and duly signed in long hand, executed in ink and stamped at the bottom right hand corner by an authorized/ empowered representative of the Bidder. The Bidder must also sign and stamp all pages of this DNIT as acceptance of all conditions contained therein and for the purpose of identifications. Financial Bid received in the format other than specified in **Schedule B** (Financial Bid) is liable to be rejected.
- 4.12 Bids must be received at the address specified in this document not later than the date and time stipulated in the DNIT. The Chief Executive Officer may, at his discretion, extend the deadline for submission of Bids. Any Bid received after the last date/ time for submission of Bids, as stipulated above, shall not be considered and will be returned.
- 4.13 Clarifications, if any, may be sought by the Bidders so as to reach GM (Works) at least seven days before last date prescribed for submission of Bids. Except for any written clarification by Chief Executive Officer, SASB which is expressly stated to be an addendum to the DNIT, no written or oral communication, presentation or explanation by any other employee of the SASB shall be taken to bind or fetter the Shrine Board under the Contract. All corrigenda, addenda, amendments and clarifications to the DNIT will be hosted on our website ([www.shriamarnathjishrine.com](http://www.shriamarnathjishrine.com)) and NOT in newspaper (s). The Bidders should keep themselves updated on this account.
- 4.14 The Technical Bid shall be opened at **10 a.m. on 24.03.2016** in the office of General Manager (works) in the presence of the authorized representatives of the Bidders who may wish to be present at that time. Bidders whose Technical Bids have been accepted shall be informed about the date and time for opening of the Financial Bids.
- 4.15 The Chief Executive Officer, SASB is not bound to accept the lowest or any Bid and may, at any time by notice in writing to the Bidders, terminate the tender proceedings without assigning any reason whatsoever.
- 4.16 The Bid should remain valid and open for acceptance for a period (i.e. Bid Validity Period) of 60 days from the last date prescribed for its receipt.
- 4.17 To facilitate evaluation of Bids, the GM (Works) may, at his sole discretion, seek clarification in writing from any Bidder regarding the Bid. The request for such clarification or substantiation and the response shall be in writing or by facsimile or email. No material change in the substance of the Bid would be permitted by way of such clarification/ substantiation.
- 4.18 The GM (Works) may award the Contract to the Bidder whose Bid has been evaluated to be responsive and who is eligible and qualified to perform the Contract satisfactorily as per the Terms and Conditions incorporated in the DNIT. The GM (Works), SASB will send to such



eligible Bidder a letter (hereinafter referred to as the 'Letter of Intent') prescribing the amount which the Shrine Board will pay to the eligible Bidder in consideration of work/ services to be executed by the eligible Bidder as prescribed in the Contract.

- 4.19 The eligible Bidder will have to enter into an Agreement with the Shrine Board, as per the Terms and Conditions mentioned in the DNIT or such other Terms that may be prescribed, within the fifteen days of the issue of Letter of Intent.
- 4.20 Chief Executive Officer, SASB reserves the right to reject all or any Bid in whole, or in part, without assigning any reason. Any enquiry after the submission of tender will not be entertained.
- 4.21 Shri Amarnathji Shrine Board shall not be responsible for release of any CDR pledged to FA/ Chief Accounts Officer, SASB without submitting his tender in the tender box. However, the CDR's of unsuccessful bidders/ eligible bidders who have paid the prescribed tender document fee shall be released only after issuance of Letter of Award (LoA) in favour of the successful bidder.

## V. **SCOPE OF WORK**

### 5.1 **The Board and the Yatra:**

- a) Shri Amarnathji Shrine Board (SASB) was established in 2001 under a statute with a view to providing better management of the Shri Amarnathji Yatra, upgradation of facilities for the pilgrims, etc. Hon'ble Governor, J&K is the ex-officio Chairman of the Board.
- b) The pilgrimage (Yatra) is undertaken during the period specified in the months of July-August, through two different routes:
  - i) Pahalgam (7500 ft.)- Panjtarni (12729 ft.) - Holy Cave (13500 ft.). This route is 32 km long from Chandanwari to Holy Cave; and,
  - ii) Baltal (9500 ft.), Domel (9577 ft.)- Brarimarg (13120 ft.)- Holy Cave (13500 ft.). This route is 14 km long from Baltal to Holy Cave.
- c) During the Yatra, over 3.5 lakh persons (this number may be exceeded this year) undertake the pilgrimage to the Holy Cave Shrine of Shri Amarnathji, situated at an altitude of 13,500 feet, in District Anantnag, J&K. Baltal (near Sonamarg) and Nunwan (Pahalgam) are the two Base Camps where the Yatris congregate before embarking on the pilgrimage. Other Camps en-route are Sheshnag, Panjtarni and Holy Cave.

### 5.2 **Site Overview**

- a) The Camps are located at varying altitudes ranging from 7500 ft to 13500 ft above MSL.
- b) Temperature ranges from (-10<sup>0</sup>C to +25<sup>0</sup>C) during Yatra period.



- c) Baltal/ Domel is connected through a motorable road on Srinagar- Leh National Highway and is 110 km away from Srinagar. Pahalgam (Nunwan) is located at a distance of 90 km from Srinagar. It is located at a distance of 38 km from Khanabal which is at 250 km on Jammu - Srinagar National Highway.
- d) The journey to Holy Cave from Baltal involves trekking a distance of 14 km. From Chandanwari (Pahalgam route), the visit to the Holy Cave involves a trek of 32 km.
- e) Average weight that can be carried manually by a *pittoo* is 20 kg and by a pony is 60 kg.
- f) The Bidders will need to acquaint themselves of the nature and quantum of work involved, preferably by undertaking site visits of the Camp locations. Considering the present weather conditions, it would be possible for a bidder to visit Nunwan Camp (Pahalgam) any day, whereas other locations can be visited only after the snow melts.

## **VI. TERMS AND CONDITIONS OF THE CONTRACT**

- 6.1 The bidders are required to quote rate above/ below percentage on SSR of 2012 shown in the rate list of Schedule-B, (Format of Financial Bid) against each item of work. However, where it has been mentioned in column V that the 'Rate to be quoted', the bidder should quote rate in Rupees per unit. All rates/ percentages should be quoted in figures and words. The bidders are also to calculate and mention total cost of his bid in last row of the table of Schedule B, both in figures and words.
- 6.2 Bids shall have to be submitted separately for each Work as indicated in the NIT.
- 6.3 The Security Deposit/ Earnest Money of the unsuccessful bidders shall be released immediately after the work is awarded to successful bidder.

### **Imbalanced bids :**

- 6.4 All Bids (received from bidders) valuing less than 90% and above 80% of the tendered cost shall be treated as imbalanced bids.
- 6.5 Bidders submitting imbalanced bids shall have to attach an additional guarantee (Earnest Money) in the shape of CDR with his bid. This Additional Earnest Money should be equal to the difference between the bid amount quoted by bidder and the cost of the work mentioned in the Notice Inviting Bids.
- 6.6 Bids amounting to less than 80% of cost mentioned in the Notice Inviting Tender shall be out rightly rejected by GM (Works) SASB and not considered.
- 6.7 The successful bidder shall have to start and complete the work on the allotted rates, within the stipulated time, failing which following penalties shall be imposed:

- (i) First 3 days of delay Penalty 1% of contract value.
- (ii) 4<sup>th</sup> day upto 10<sup>th</sup> day 2% of contract value.
- (iii) Beyond 10 days Earnest Money shall be forfeited and the contract shall automatically stands cancelled. The General Manager Works, GM (Works), SASB shall be at liberty to get the work done through another suitable agency at the risk & cost of the contractor without issuing any notice to the Contractor / Firm.

- 6.8 Not with standing Clause -6.7 above in case progress of work is found to be slow, the Engineer In-charge shall be free to supplement the engagement of labour skilled/ unskilled or by engaging another agency in the interest of speedy execution of work.
- 6.9 The quantum of work can be increased or decreased as per the requirements and site conditions. The payment of extra work involved, if any, shall be paid as per SSR rates mentioned in the Allotment of Contract along with percentage increase/ decrease allowed on the rates allotted for each item of work in Work Allotment Letter.
- 6.10 The Contractor shall start the work only after taking demarcation (nishandehi) from the site Engineer concerned and shall execute the work strictly as per the specification provided in Work Allotment Letter.
- 6.11 The date of start of work shall be reckoned by the site Engineer In-charge, keeping in view the feasibility of commencing the work at site.
- 6.12 The Contractor shall submit pictorial evidence (Photographs) of execution of work (post execution, during execution and after completion of work) with his claim.
- 6.13 The Contractor shall be bound by the Rules and Regulations with regard to issue and purchase of Stores, Stock and other materials etc. and also the tender conditions incorporated in the tender document for the said work. The Contractor shall be responsible for arrangement of all the items required for completion of the work in time, like Electricity, Water, Manpower, Tools and Equipment etc.
- 6.14 The Contractor shall stand guarantee for the workman-ship in respect of the material used in the construction and if any material used is found defective in quality, the Contractor shall have to get it replaced on spot, free of charge, and the cost of dismantling the defective construction and its re-construction shall be responsibility of the contractor.
- 6.15 The Contractor shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the state or Central Government or local authority and any other labour law (including rules), regulation, byelaws that may be passed or notification that may be issued under any labour law in future either by the state or the Central Government or the local authority. The Contractor shall be solely responsible for failure, if any, for liabilities,

adherence to the labour, laws, local laws and other related rules/ regulations.

- 6.16 All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract shall be the sole responsibility of the contractor.
- 6.17 The Contractor shall provide Insurance Cover from date of start to date of completion of work to the Labour/ employees, employed by him for execution of work against any personal injury or death.
- 6.18 The employees hired/ employed for the execution of work of the contractor shall in no case whatsoever, be treated as the employees of SASB.
- 6.19 **Child Labour:** No child labour shall be engaged, the employment of child labour is strictly prohibited in any construction works and Contractor shall abide by the law.
- 6.20 The Contractor is bound to draw an agreement with GM (Works), SASB within fifteen days from the date of issuance of Allotment Order.
- 6.21 GM (Works), SASB shall be at liberty to suspend the agreement due to any *Force Majeure* conditions such as Government regulations, **court orders, wars, accidents creating disturbed conditions, terrorist activity, strikes/riots, civil commotion etc.**
- 6.22 All disputes and differences between the parties arising out and relating to the agreement to be signed between the GM (Works) SASB and the firm, including the interpretation of its Terms and Conditions shall be referable to the Sole Arbitrator to be nominated by the Chief Executive Officer, Shri Amarnathji Shrine Board whose decision shall be final and binding upon all the parties.
- 6.23 All questions relating to arbitration shall be determined in accordance with the provisions of J&K Conciliation and Arbitration Act, 1997 and, Courts in the State of Jammu & Kashmir alone shall have the Jurisdiction to deal with such questions.
- 6.24 The rates quoted by the contractor shall be inclusive of all taxes e.g. (sales tax, service tax etc) that are in vogue.
- 6.25 If during the period of three months from the date of completion, the work - defects which have been caused by bad workmanship, use of inferior materials on the work, the Contractors shall be liable to remove the defects or make repairs at his own cost and expenses within a period of three days of the receipt of notice from the Deputy General Manager (works), Shri Amarnathji Shrine Board to that effect and in the event of his failure to remove these defects within the stipulated period,

the cost thereof shall be recoverable from the security deposit of the contractor or from payments due to him.

**VII Payment Clause:**

- 7.1 Payment shall be made to the Contractor for complete item of the work including cost of the material and labour (finished) after recording the measurement in the **Works Register** by the Junior Engineer In-charge site (To be maintained for each work at site) duly checked by the Deputy General Manager Works.
- 7.2 The payment to the bidder shall be made after successful completion of work within the stipulated time (with specification as per the allotment of Contract and subsequent drawal of agreement) after satisfactory use/ function of the work during complete Yatra Period

## **SCHEDULE A (TECHNICAL BID)**

### **PART A: DETAILS OF COST OF DNIT AND EARNEST MONEY**

#	Item	Details
1	Amount and details of payment towards the cost of DNIT	Rs. <i>(in words)</i> :
		Receipt No./Cheque No:
		Date:
2	Amount and details of Earnest Money Deposit submitted	Rs. <u>(in words)</u> :
		DD No.
		Dated:
		In favour of
		Date of issue:
		Issuing Authority:

### **PART – B: BASIC DETAILS ABOUT THE AGENCY.**

i) Name and address of : Name: \_\_\_\_\_  
the Agency.

Address: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Phone: \_\_\_\_\_

E-mail: \_\_\_\_\_

## **PART- C: DOCUMENTS ESTABLISHING BIDDERS ELIGIBILITY.**

The Bidder is required to furnish the following information/ documents:

*(please attach separate sheets where necessary):*

1. Registration No. / Other documents of the Agency (attach a certified copy of Registration Certificate/ other documents; *please see DNIT – Para 3.1 of ‘Documents Establishing Bidder’s Eligibility’*)
2. The Bidder must furnish certified copies of bank statement - *please see DNIT – Para 3.2 of ‘Documents Establishing Bidder’s Eligibility’*

#	Financial Year	Turnover (Rs.)
1	2011-12	
2	2012-13	
3	2013-14	
4	2014-15	

3. Documents to show that the contractor posses relevant experience in past three years. The Bidder must furnish certified documents like Letter of Award/ Offer, Work Order, Contract Agreement, Certificate of Completion etc. indicating experience and execution of similar works for fulfilling the eligibility criteria and also furnish information in following format (please add rows as necessary for other sectors, if applicable) - *Para 3.3 of Documents Establishing Bidder’s Eligibility*

S. No.	Name of work	Name of Client	Value of Completed work (Rs.)	Date of commencement	Date of completion	Whether supporting documents (attested) enclosed (Yes/No)

4. Certified copy of PAN Card - *Para 3.4 of ‘Documents Establishing Bidder’s Eligibility’*)
5. Certified copy of TIN Registration Certificate – *Para 3.5 of ‘Documents Establishing Bidder’s Eligibility’*)
6. General Profile of the Bidder – *Para 3.6 of ‘Documents Establishing Bidder’s Eligibility’*)
7. Affidavit on Rs. 10/- Stamp paper stating that every information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against the bidder. Agency. Please attach the affidavit - *Para 3.7 of Documents Establishing Bidder’s Eligibility*

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Assembling of Toilet/ Baths (500 nos.)and fixing of P.V.C pipes with minor repairs (welding and denting) including aligning and clearance of choked sewer line and cost of dismantling / stacking after culmination of Yatra – 2016 at Baltal Camp.

**S.No. : 01**

**Adv.Cost: 4.80 lac**

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Engagement of labour for Repair of toilets/baths i) Blacksmith 1 <sup>st</sup> class ii) Helper	30 30	Day Day	Rs 450/- Rs.300/-		
2	Supplying of various fitting items for Repairs to doors of toilets/baths at Baltal. i) Mild Steel Sliding Door Bolt(150mm) ii) M.S.Tower Bolt 150x10mm iii) M.S.Handles(125mm) iv) Supply of Nuts and Bolts	50 100 100 150	No. No. No. Kg	Rs 90/- Rs 49.35/- Rs 25.90/- Rs 75/-		
3	Erection of toilets/baths at different location including head load of material from store to erection site (before start of Yatra). Including refixing of 100 No. bases in proper alignment on back side of langer 5-6 and repair /laying damaged sewer line in CRPF Camp	500	No.	RTQ		
4	Supply and fixing of PVC pipes and other fittings items to toilets/baths. I. PVC pipes(110mm) II. PVC bends(110mm) III. PVC sockets(110mm) IV. PVC Tee(110mm) V. Door Tee(110mmx110mmx110mm)	500 300 150 150 15	Rm No. No. No. No.	Rs 160/- Rs 114/- Rs 85/- Rs 152/- Rs 185/-		
5	Hire charges of Gen. Set,welding set and welding rod's etc.	10	Day	RTQ		
6	Engaging labour for maintenance of toilets/baths during Yatra	60	Day	Rs.300/-		
7	Dismantling of toilets/baths at erection site including carriage of material from erection site to store with proper stacking after conclusion of Yatra.	50	No.	RTQ		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**





## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Assembling of Toilet/ Baths (395 nos.) with minor repairs (welding and denting), fixing of P.V.C pipes, cleaning/ excavation of earthen disposal pits including cost of dismantling/stacking of Toilets/Baths at enroute Rang morh to Domel and Neelgrath Helipad area

**S.No.: 02**

**Adv.Cost: 6.30 lac**

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Engagement of skilled and semi-skilled labour for Repair to toilets/baths. i) Blacksmith 1 <sup>st</sup> class ii) Helper iii) Welding set	30 10 18	Day Day Day	Rs 450/- Rs.300/- RTQ		
2	Supplying of various fitting items for Repairs to doors of toilets/baths at En-route RangaMorh to Domel i) Mild Steel Sliding Door Bolt(150mm) ii) M.S.Tower Bolt 150x10mm iii) M.S.Handles(125mm) iv) Supply of Nuts and Bolts	30 100 100 150	No No. No. Kg	Rs 90/- Rs 49.35/- Rs 25.90/- Rs 75/-		
3	Erection of toilets/baths at different location including head load of material from store to erection site (before start of Yatra).	395	No.	RTQ		
4	Supply and fixing of PVC pipes and other fittings items to toilets/baths. I. PVC pipes(110mm) II. PVC bends(110mm) iii. PVC sockets(110mm)	495 300 100	Rm No. No.	Rs 160/- Rs 114/- Rs 85/-		
5	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.	149.50	Cum	Rs. 240.45/-		
6	Cleaning of the existing disposal pits manually and disposing the decomposed debris at appropriate site pits (size 8'x4'x4' )manually	160	Day	Rs.300/-		
7	Covering the pits including carriage of					

	material from store to site of work manually	247	Day	Rs.300/-		
8	Supply of CGI sheets for covering the pits 0.63mm @ 3 sheets/pit for such 15 no.x3 =45	600	Kg	Rs.60/-		
9	Carriage of material from SASB store to site of work by engaging LMV	15	Day	RTQ		
10	Dismantling of toilets/baths at erection site including carriage of material from erection site to store with proper stacking after conclusion of Yatra.	395	No.	RTQ		

**Total cost of bid (to be quoted both in figures and words)**

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Construction of two no. sheds (size: 20'x12') for Food Supply Department, one no. Shed (size: 20'x12') for Labour Department, one no. Medical Shed (size: 12'x12') at Domail for Medical Deptt., one no. shed for Kitchen of PHE Department (size: 15'x12'), one no. shed for HP Gas (size: 20'x12'), one no. Shed for PDD (size: 12'x12'), two no. frisking shed (size: 10'x30') and one no. (20'x40') for cloak room , 03 no. Gas Store ( 10'x30') for storage of HP Gas for langars and dismantling after culmination of Yatra including stacking in SASB store properly at Baltal.

**S.No.: 03**

**Adv.Cost: 5.20 lac**

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes upto 0.50cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mtr and lift upto 1.5 mtr in all kinds of soil. By manual means.	135	No.	Rs.24.90/-		
2	Providing wood work in frames of false ceiling, partitions etc sawn and fixed in position. Budloo/Fir wood i) New Wood ii) Old Wood	1.691 5.075	Cum Cum	Rs 42755.75/- Rs 12755.75/-		
3	Providing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m <sup>2</sup> i) New Sheet ii)Old Sheet	139.31 784.96	Sqm Sqm	Rs 757.00/- Rs 219.82/-		
4	Dismantling wood work in frames,					

	trusses, purlins and rafters upto 10 m span and 5 meter height including stacking material within 50 meter lead	6.767	Cum	Rs 1767.10/-		
5	Dismantling roofing including ridges, hips, valleys and gutters etc and stacking material within 50 meter lead of G.S. sheet	784.96	Sqm	Rs. 62.25/-		
6	Carriage of material from Srinagar to Baltal by engaging LMV	01	Day	RTQ		
7	Carriage of store material from SASB store to site of work.	30	Day	Rs.300/-		
8	Carriage of material from site of work to SASB store after conclusion of yatra by engaging LMV	01	Day	RTQ		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Improvement to existing sewer line of toilet/ baths by way of providing additional 250 mm dia RCC Spun pipe length 370 meter at Baltal. (RCC spun pipe to be supplied departmentally)..

**S.No.: 04**

**Adv.Cost: 3.00 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil	438.25	Cum	Rs 240.45/-		
2	Providing and laying in position cement concrete of specified grade excluding cost of centring and shuttering all works upto plinth level. 1:4:8 (1 cement: 4 course sand:8 graded stone aggregate 40mm nominal size) Crushed.	2.862	Cum	Rs 3112.80/-		
3	Brick work with common burnt clay FPS (non modular) bricks of class designation 75 in foundation and plinth in cement mortar 1:4 (1 cement 4 course sand)	8.496	Cum.	Rs 4845.90/-		
4	Providing, hoisting and fixing upto floor five level precast reinforced cement concrete work in string course, bands, coping, bed plates, anchor blocks, plain window sills and the like including cost of required centring shuttering finishing smooth with 6mm thick cement mortar 1:3 (1 cement: 3 fine sand) on exposed surfaces complete but excluding cost of reinforced with 1:2:4 (1 cement: 2 fine sand 4graded stone aggregate 20mm nominal size)	2.453	Cum	Rs 5639.45/-		
5	12mm thick cement plaster on fair side of wall in 1:4 (1 cement : 4 course sand)	37.174	Sqm	Rs. 158.65/-		
6	Reinforcement for RCC work including straightening, cutting, bending, placing					

	in position and binding all complete. Hot rolled deformed bars	371.56	Kg	Rs.71.00/-		
7	Providing and laying non-pressure NP2 class (light duty) RCC pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1: cement 2: fine sand) including testing of joints etc. complete 250mm dia RCC pipe.	369.81	Rm	Rs.505.90/-		
8	Carriage of Bricks by mechanical means avg. Lead 100km	4052	1000 No.	Rs1893.54/-		
9	Carriage of material (sand and bajree) by mechanical means avg. lead 65km.	9.742	Cum	506.23/-		
10	Carriage of RCC spun pipe from Srinagar to Baltal avg. Lead 110km	369.81	Rm	Rs.64.71/-		
11.	Carriage of cement and steel from Srinagar to Baltal by mechanical means avg. Lead 110km	2.653	Ton	Rs.64.71/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**



## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Laying of sub distribution GI pipe line 15 mm dia for water supply at enroute Ranga Morh to Domel and in Langar store area including cost of its dismantling/stacking after culmination of Yatra at SASB store.

**S.No.: 05**

**Adv.Cost: 2.30 lac**

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Laying of G.I pipes complete with G.I fittings including trenching and refilling etc.(excluding cost of pipe) (Ext. work). 15mm dia, nominal bore, medium	1000	Rm	Rs 45.75/-		
2	Providing and fixing of G.I pipes complete with G.I fittings including trenching and refilling etc. (Ext. work). 15mm dia, nominal bore, medium	600	Rm	Rs 133.75/-		
3	Providing and fixing of GI fittings: (i) 20mm to 15mm Sockets (ii) 15mm dia GI Elbow (iii) 15mm dia GI Tee(equal) (iv) 15mm dia GI Union	200 200 150 40	No. No. No. No.	Rs 18.00/- Rs 26.00/- Rs 38.00/- Rs 174.80/-		
4	Providing and fixing brass stop cock of approved quantity.(15mm dia)	40	No.	Rs 224.05/-		
5	Providing and fixing PTMT Bib cock ordinary of approved quality	330	No.	RTQ		
6	Carriage of pipes and other fittings from Ganderbal to Baltal by M.T.	01	Day	RTQ		
7	Engagement of plumber for maintenance of water supply during Yatra period.	20	No.	Rs.450.00/-		
8	Dismantling of G.I. Pipe with fitting after conclusion of Yatra	1600	Rm	Rs12.80/-		
9	Carriage of dismantled material from SASB store to Site of work manually	40	Day	Rs.300.00/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Plantation of Reed plant in Oxidation Chambers of STP at Baltal.

**S.No.:** 06

**Adv.Cost:** 0.60 lac

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Supply of sand including 5km lead	63.54	Cum	Rs 364/-		
2	Supply of Reed Plants	1200	No.	RTQ		
3	Carriage of plants from source of site by LMV	01	Day	RTQ		
4	Plantation of Reed including watering etc. complete	40	No.	Rs 300/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Turfing of STP and Grease Trap area at Baltal

**S.No.: 07**

**Adv.Cost: 1.18 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil	40.38	Cum	Rs 240.45/-		
2	Carriage of earth by mechanical means avg. Distance 5km	40.38	Cum	Rs.158.52/-		
3	Filling of available earth including watering and ramming complete	40.38	Cum	Rs.102.30/-		
4	Turfing the area including watering and carriage of turf	5703.50	Sft	RTQ		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Laying of Precast cement concrete tile on foot path from Grease Trap to Prefab toilet/ Baths on back side of Langar No. 1-6 via STP at Baltal.

**S.No.: 08**

**Adv.Cost: 0.80 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15cm deep and disposal of rubbish lead upto 50m and lift upto 1.5m in all kinds of soil	356.87	Sqm	Rs 1135.95/-		
2	Fixing of precast tiles over base of cement concrete 1:4:8. 75mm thick and grouting with cement mortar 1:3 ratio including all carriages/ lead and lift (complete item)	3840	Sft	Rs.120.00/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Providing of fire gaps and paths in between tent- age area by way of excavation of drain, earth work filling and laying of RBM at Baltal

**S.No.: 09**

**Adv.Cost: 1.90 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Earth work in excavation by manual means over areas ( exceeding 30 cm and upto 1.5m in depth, 1.5 m in width as well as 10 sqm on Plan ) including disposal of excavated earth upto 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	198	Cum	Rs 240.45/-		
2	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rabish, lead upto 50m and lift upto 1.5m in all kinds of soil:	1320	100 Sqm	Rs.1135.95/-		
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. Layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering lead upto 50m and fit upto 1.5m.	198	Cum	Rs.102.20/-		
4	Supply of Nallah bed material including 2km lead (53 to 22.40mm size)	99	Cum	Rs.536.62/-		
5.	Spreading of RBM uniformly on paths.@ 2 Labour/ 1cum	198	Day	Rs.300/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Laying of precast cement concrete tile flooring from Main Road to Gate No. 2 via frisking at Baltal.

**S.No.: 10**

**Adv.Cost: 0.80 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15cm deep and disposal of rubbish lead upto 50m and lift upto 1.5m in all kinds of soil	356.87	Sqm	Rs 1135.95/-		
2	Fixing of precast tiles over base of cement concrete 1:4:8. 75mm thick and grouting with cement mortar 1:3 ratio including all carriages/ lead and lift (complete item)	3800	Sft	Rs.120.00/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Clearance/ Improvement of choked drain inside Baltal Camp and Helipad area including its reconstruction with dry random rubble masonry stone at Baltal Camp. Approx. Length 1500 mtrs.

**S.No.: 11**

**Adv.Cost: 1.60 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Slip Clearance in soils mixed with moorum / Kankar / shingle / boulders; disposal lead upto 50 metre and lift upto 1.5 mtr	270	Cum	Rs 158.95/-		
2	Earth work in excavation by manual means over areas ( exceeding 30 cm and upto 1.5m in depth, 1.5 m in width as well as 10 sqm on Plan ) including disposal of excavated earth upto 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil for lead of 01 Km	108	Cum	Rs.346.84/-		
3	Dry random rubble masonry with hard stone in foundation and plinth using nallah stone without bond stone for a lead of 1 Km	54.00	Cum	Rs.1442.26/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012

**Signature of the Bidder**

**DGM (W) Baltal**



## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Erection of CGI sheet walling for partitioning of STP and Langars, providing and fixing of agro-net partition in front of ladies toilet/bath including cost of its dismantling /stacking after culmination of yatra at Baltal Base Camp.

**S.No. : 12**

**Adv.Cost: 0.75 lac**

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil	12.234	Cum	Rs 240.45/-		
2	Fixing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m <sup>2</sup>	333	Sqm	RTQ		
3	Providing Wood work in frames of false ceiling, partitions etc. sawn and fixed in position. Budloo/ Fire wood. i) New Wood ii) Old Wood	31.68 1.495	Cft Cum	RTQ Rs.12755.75/-		
4	Supply and fixing of Agro-net around partition in front of Ladies Toilets/Baths complete	2400	Sft	RTQ		
5	Carriage of material from SASB store to site of work manually.	20	Day	Rs.300/-		
6	Carriage of wood from Ganderbal to site of work at baltal by LMV	01	Day	RTQ		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised **SSR of 2012**.

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Providing and Fixing of G.I. Pipe Railing 50mm dia at frisking point at Baltal.

**S.No.: 13**

**Adv.Cost: 0.90 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Providing and fixing of G.I pipes complete with G.I fittings including trenching and refilling etc (Ext. work).	170.73	Rm	Rs 406.65/-		
2	Earth work in excavation by manual means in over areas ( exceeding 30cm and upto 1.5mtr in depth, 1.5m in width as well as 10sqm on plain) including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil	4.58	Cum	Rs.240.45/-		
3	Providing and laying in position cement concrete of specified grade excluding cost of centring and shuttering all works upto plinth level. 1:3:6 (1 cement: 3 course sand:6 graded stone aggregate 20mm nominal size) Nallah	4.58	Cum	Rs.3552.50/-		
4	Centring and shuttering including strutting, propping etc. removal of frame work for foundations, footings, bases of columns etc. for mass concrete .	29.55	Sqm	Rs.179.25/-		
5	Carriage of material (sand and bajree) 5km lead.	6.18	Cum	Rs.127.08/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work :** Repair/ Re-erection of barbed wire fencing, fencing of old Helipad area ,Medical Camp at Domel , damaged fencing to STP area and Grease Trap including cost of its dismantling/stacking after culmination of Yatra at Baltal Camp.

**S.No.: 14**

**Adv.Cost: 3.40 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil	4.779	Cum	Rs 240.45/-		
2	Excavating holes up to 0.50 cum including getting out the excavated soil, then returning the soil as requires in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mtr. and lift upto 1.5 mtr. in all kinds of soil, by manual means.	106	No.	Rs 24.90/-		
3	Suppling of steel angle iron posts and struts of required size including bottom to be split/bent at right angle in opposite direction for 10cm length and drilling holes upto 10mm dia etc. complete.	1035.02	Kg	Rs 73.50/-		
4	1.8m high fencing with 2.4 m angle iron 50x50x6mm posts placed every 3m centre to centre embedded in cement concrete blocks, every 15 <sup>th</sup> post, last but one end post and corner post shall be strutted on both sides and end post on side only, provided with 12 horizontal lines and two diagonals inter woven with horizontal wires of barbed wire 9.38kg per 100m (min) between two posts fitted and fixed with GI staples, turn buckles etc. complete, (Cost of posts, struts, earth work and concrete to be paid for separately).	1804	Rm	Rs 64.30/-		

	With GI barbed wire.					
5	1.8m high fencing with 2.4 m angle iron 50x50x6mm posts placed every 3m centre to centre embedded in cement concrete blocks, every 15 <sup>th</sup> post, last but one end post and corner post shall be strutted on both sides and end post on side only, provided with 12 horizontal lines and two diagonals inter woven with horizontal wires of barbed wire 9.38kg per 100m (min) between two posts fitted and fixed with GI staples, turn buckles etc. complete, (Cost of posts, struts, earth work and concrete to be paid for separately). With GI barbed wire.	500.00	Rm	Rs. 153.90/-		
6	Providing and laying in position cement concrete of specified grade excluding cost of centering and shuttering all works upto plinth level. 1:2:4 (1 cement: 2 course sand:4 graded stone aggregate 40mm nominal size) Crushed	4.779	Cum	Rs.4575.50/-		
7	Centering and shuttering including strutting, propping etc. removal of frame work for foundations, footings, bases of columns etc. for mass concrete and	41.82	Sqm	Rs.179.25/-		
8	Strengthening of damaged angles i) Blacksmith 1 <sup>st</sup> class ii) Helper	20 20	Day Day	Rs450/- Rs.300/-		
9	Carriage of material (sand and bajri) by mechanical means avg. lead 65km.	6.45	Cum	506.23/-		

**Total cost of bid (to be quoted both in figures and words)**

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Mounting of water storage tank on existing stages, water supply fitting, fixing of 02 nos. motor pump and fixing of chain link fencing including cost of its dismantling/stacking after culmination of Yatra at Neelgrath

**S.No.: 15**

**Adv.Cost: 0.80 lac**

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Providing and fixing of G.I. pipes complete work G.I fittings including trenching and refilling etc. 15 mm dia, nominal bore, medium	400	Rm	Rs.133.75/-		
2	Providing and fixing of GI fittings. (i) 20mm to 15mm Sockets (ii) 15mm dia GI Tee (iii) 15mm dia GI Union	30 30 15	No. No. No.	Rs 18/- Rs 38/- Rs.174.80/-		
3	Providing and fixing of brass stop cock of approved quality(15mm nominal bore)	04	No.	Rs.224.05/-		
4	Providing and fixing of PTMT Bib cock of approved quality	10	No.	Rs 154.35/-		
5	Supply of labour skilled/unskilled for mounting of water storage tanks on existing staging, water supply fitting 02 No. motor.bentup pipes and chain link fencing ( material available in SASB store) i) Plumber ii) Helper iii) Blacksmith	06 06 06	Day Day Day	Rs.450/- Rs.300/- Rs.450/-		
6	Supply of nuts 7 Bolts for fixing of chain link fencing	10	Kg	RTQ		
7	Supply of plumber for maintenance of water supply during Yatra for 20 days	20	Day	Rs.450/-		
8	Dismantling of water supply pipe, water storage tank, motor pumps, bentup pipes and chainlink fencing after the culmination of Yatra i) Plumber ii) Helper iii) Blacksmith	04 06 04	Day Day Day	Rs.450/- Rs.300/- Rs.450/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Construction of (02 no.) fuel depot including cost of its dismantling/stacking after culmination of Yatra at Neeelgrath.

**S.No. : 16**

**Adv.Cost: 0.35 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Excavating holes up to 0.50 cum including getting out the excavated soil, then returning the soil as requires in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mtr. and lift upto 1.5 mtr. in all kinds of soil, by manual means.	16	No.	Rs 24.90/-		
2	Providing Wood work in frames of false ceiling, partitions etc. sawn and fixed in position. Budloo/ Fire wood.	36.96	Cft	RTQ		
3	Fixing corrugated P.P.G.I sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m <sup>2</sup> (Labour only)	40.613	Sqm.	RTQ		
4	Filling empty cement bag with sand/ earth including cost of sewing and strings: excluding cost of bag and earth/ sand	400	No.	Rs 3.70/-		
5	Supply of empty cement bags	400	No.	RTQ		
6	Dismantling wood work in frames, trusses, purlins and rafters upto 10 meters span and 5 metres height including stacking the material within 50 metres lead of sectional area below 40 square centimetres	136.58	Rm	Rs.7.05/-		
7	Dismantling of PPGI roofing including ridges, hips, valleys and gutters etc. and stacking the material within 50 metres lead .	40.613	Sqm	RTQ		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder DGM (W) Baltal**



## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Repairs/Painting of Pre-fabricated Huts (40 nos) at Baltal

**S.No.: 17**

**Adv.Cost: 1.40 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Removing oil bound distemper, water proofing cement paint and the like by scrapping and sand papering and preparing the surface smooth, including necessary repairs to scratches etc. complete.	998.20	sqm	Rs 8.80/-		
2	Distemping with Oil bound washable distemper of approved brand and manufacture to give an even shade.	3327	sqm	Rs 31.55/-		
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. One or more coats on old wood work	694	sqm.	Rs 45.65/-		
4	Painting (one or more coats) with black Japan paint of approved brand and manufacture to give an even shade	83.92	sqm	Rs 41.20/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**



## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Painting of Prefabricated toilet/ baths at Baltal Base Camp, Rangamorh to Domel including Neelgrath Helipad (300 nos.).

**S.No. 18**

**Adv.Cost: 3.00 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc (10%)	621	Sqm	Rs.6.75/-		
2	Applying priming coat with ready mixed red oxide Zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works. (10%)	621	Sqm	Rs.27.80/-		
3	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade on old steel work ( one or more coat) (100%)	6228	Sqm	Rs.45.60/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SC HEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Re-roofing and Painting of Hangar including Dismantling/stacking of roofing after the conclusion of yatra at Baltal.

**S.No.: 19**

**Adv.Cost: 2.40 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Repairs to steel trusses of Hangar including strengthening of truss by way of welding including erection of two no. room 8'x12' in OPD at Baltal.  i. Black smith ii. Mazdoor	16 16	No. No.	Rs 450/- Rs 300/-		
2	Providing corrugated PPGI sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m <sup>2</sup> (Labour only)	706.28	kg	RTQ		
3	Providing ridges or hips of width 60 cm overall width overall width plain G.S. sheets fixed with polymer coated J or L hooks, bolts and nuts 8mmdia G.Ilimpet and bitumen washers complete 0.63mm thick with zinc coating not less than 275gm/m <sup>2</sup> .	15.24	Rm	Rs 490.40/-		
4	Structural steel work in single section fixed with connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	810	kg	Rs 69.60/-		

5	Providing PVC sheet 2mm thick	145.72	sqm	Rs 376/-		
6	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	363.19	sqm	Rs 8.80		
7	Distempering with Oil bound washable distemper of approved brand and manufacture to give an even shade. Old work (one or more coats)	788.84	sqm	Rs 31.55/-		
8	Refixing of ceiling of Hanger rooms damaged in winter i. Carpenter ii. Helper	12 12	No. No.	Rs 450/- Rs 300		
9	Ply wood 5 ply with commercial ply on both faces 6mm thick (panels)	31.22	sqm	Rs 450/-		

**Total cost of bid (to be quoted both in figures and words)**

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Re-roofing/ renovation and painting/ white washing of pacca toilet including its cost of dismantling after culmination of Yatra at Baltal.

S.No. : 20

Adv.Cost: 2.00 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Repairs to steel structure of roofing. 1. Black smith 1st class: 2. Mazdoor:	10 20	Day Day	Rs 450/- Rs 300/-		
2	Providing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m <sup>2</sup> (Labour only)	323.42	Sqm	Rs 219.80/-		
3	White washing with lime to give an even shade. New work(three or more coats)	579.64	Sqm	Rs 15.90/-		
4	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade. Old steel work (one or more coats)	393.58	Sqm	Rs 45.65/-		
5	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50m lead	38.232	Cum	Rs 813.85/-		
6	Providing and laying in position cement concrete of specified grade excluding cost of centring and shuttering all works upto plinth level. 1:4:8 (1 cement: 4 course sand:8 graded stone aggregate 40mm nominal size) Nallah	2.124	Cum	Rs 3061.3/-		
7	Cement concrete flooring	27.881	Sqm	Rs 314.20/-		

	1:2:4 (1 cement: 2 course sand:4 graded stone aggregate) finished with floated coat of neat cement including cement slurry but excluding cost of nosing of steps etc. complete 40mm thick with 20mm nominal size stone aggregate) Nallah					
8	Providing and fixing white vitreous china water closet squatting (Indian type) Orrissa pattern W.C pan of size 580mm.	20.00	No.	Rs1210.80/-		
9	Supply and fixing of PVC pipes and other fitting items to toilets/ baths i. PVC Pipes(110mm) ii. PVC Bends(110mm) iii. PVC Socket(110mm) iv. PVC Tee (110mm) v. Door Tee(110x110x110mm)	60 25 20 20 04	Rm. No. No. No. No.	Rs 160/- Rs 114/- Rs 85/- Rs 152/- Rs 185/-		
10	Carriage of material from Srinagar (Factory) to Baltal (110km lead)	0.834	tonn	Rs 683.10/-		
11	Carriage of material (sand and bajree) by mechanical means avg. lead 5.00km.	4.372	cum	Rs 127.08/-		
12	Carriage of material from Ganderbal to Baltal	01	Trip	RTQ		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Laying of sub distribution GI pipe line 15mm dia for water supply in Baltal Camp and old Helipad area including cost of its dismantling /stacking after conclusion of yatra at Baltal camp.

**S.No.: 21**

**Adv.Cost: 1.75 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Laying of G.I pipes complete excluding cost of pipe (Ext. work). 15mm dia, nominal bore, medium	850	Rm	Rs 12.80/-		
2	Laying of G.I pipes complete including trenching and refilling etc.(excluding cost of pipe) 15mm dia, nominal bore, medium	900	Rm	Rs 45.75/-		
3	Providing and fixing of GI fittings: i. Socket (15-20mm) ii. Elbow (15mm) iii. Tee (15mm) iv. Union (15mm)	100 100 100 50	No. No. No. No.	Rs 18/- Rs 26/- Rs 38/- Rs 174.80		
4	Providing and fixing brass stop cock of approved quantity. (15mm nominal bore)	50	No.	Rs 224.05/-		
5	Providing and fixing PTMT Bib cock (ordinary)	500	No.	Rs 100/-		
6	Carriage of pipes and other fittings from Ganderbal to Baltal by M.T.	01	trip	RTQ		
7	Engagement of plumber for maintenance of water supply during Yatra period.	30	No.	Rs 450/-		
8	Dismantling of GI pipe after conclusion of yatra and carriage of material upto store	1750	Rm	Rs 12.80		
9	Carriage of dismantled material from SASB store to Site of work	20	No.	Rs 300/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**



## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Assembling of Toilet/ Baths (160 nos.) including fixing of P.V.C. pipes, with minor repairs and cleaning/ excavation of earthen disposal pits including cost of dismantling/ stacking of toilets/baths after the culmination of yatra at enroute Domail to Holy Cave

**S.no : 22**

**Adv.Cost: 3.20 lac**

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Engagement of labour for repair of toilets/baths Blacksmith (2nd class) Helper	10 10	Day Day	Rs 400/- Rs.300/-		
2	Supply of various fitting items to the toilets and baths. VI. PVC pipes VII. PVC bends VIII. PVC sockets IX. Nuts & Bolts	200 140 50 50	Rm No. No. Kg	Rs.160/- Rs 114/- Rs.85/- Rs. 75/-		
3	Erection of toilets/baths at different location including head lead of material from store to erection site (before start of Yatra)	160	No.	RTQ		
4	Dismantling of toilets/baths at erection site including carriage of material from erection site to store with proper stacking after conclusion of Yatra.	160	No.	RTQ		
5	i.Earthwork in excavation by manual means in trenches for foundations, drains, pipes, cables etc (not exceeding 1.5 mtr in width) and for shafts, wells cesspits and the like not exceeding 10 sqm on plan depth upto 1.5 mtr including disposal of excavated earth upto 1 mtr from cuttings edge , disposed earth is to be leveled and neatly dressed in all kind of soil. ii. For covering the new excavated pits manually.	145 40	Cum. Day	Rs. 240.45/- Rs.300/-		
6	Cleansing of the existing disposal pits manually and disposing the decomposed debris at appropriate site (pits size 8'x4'x4') including covering these pits manually	80	Day	Rs.300/-		
7	Carriage of toilets/baths from Panjtarni to Sangam by head load ( No. of Toilets/ baths)	25	No.	RTQ		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**



## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Assembling of Toilet/ Baths (259 nos.) including fixing of P.V.C. pipes, with minor repairs and cleaning/ excavation of earthen disposal pits including its cost of dismantling/ stacking of toilets after the culmination of yatra at Holy Cave Camp

**S.No. : 23**

**Adv.Cost: 4.90 lac**

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Engagement of labour for repair of toilets/baths Blacksmith (2nd class) Helper	15 15	Day Day	Rs 400/- Rs.300/-		
2	Supply of various fitting items to the toilets and baths. I. PVC pipes II. PVC bends III. PVC sockets IV. Nuts & Bolts	250 200 50 80	Rm No. No. Kg	Rs.160/- Rs 114/- Rs.85/- Rs. 75/-		
3	Erection of toilets/baths at different location including head lead of material from store to erection site (before start of Yatra)	259	No.	RTQ		
4	Dismantling of toilets/baths at erection site including carriage of material from erection site to store with proper stacking after conclusion of Yatra.	259	No.	RTQ		
5	Earthwork in excavation by manual means in trenches for foundations, drains, pipes, cables etc (not exceeding 1.5 mtr in width) and for shafts, wells cesspits and the like not exceeding 10 sqm on plan depth upto 1.5 mtr including disposal of excavated earth upto 1 mtr from cuttings edge, disposed earth is to be leveled in all kind of soil.	253.75	Cum.	Rs. 240.45/-		
6	Cleansing of the existing disposal pits manually and disposing the decomposed debris at appropriate site (pits size 8'x4'x4') (Mazdoor)	120	Day	Rs.300/-		
7	Engagement of labour for covering the pits including the carriage of material from store to site of work (mazdoor)	195	Day	Rs.300/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Assembling of prefabricated huts (09 nos.) with minor repairs including cost of its dismantling and carriage/ stacking after the culmination of yatra at Holy cave Camp

**S.No.: 24**

**Adv.Cost: 5.40 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Repairs to the structure of New Huts by engaging skilled labours and providing of additional members with required nuts and bolts and also for dismantling of steel structure. Blacksmith (1st class) Helper	18 18	Day Day	Rs 450/- Rs.300/-		
2	Fixing of Puf Panels for side walls of huts, roofs etc including fixing of doors, windows at appropriate position and strengthening with M.S. channels for joining of Puf Panels with required nuts and bolts complete.	9020	Sft	RTQ		
3	Head load of puff Panels and channels from SASB store upto Hut site including fixing floors, doors and windows i. Carpenter (1st class) ii. Helper iii. labour	18 09 90	Day Day Day	Rs 500/- Rs.300/- Rs.300/-		
4	Fixing of wood work in frames of false ceiling etc, sawn and fixed in position.	1.98	Cum	Rs. 12755.55/-		
5	Fixing of hardboard ceiling sheet of approved quality with necessary nails etc completely (frame work to be paid separately) 4 mm thick	214.29	Sqm.	Rs. 296.70/-		
6	Providing and applying the priming coat with synthetic enamel paint of approve brand and manufacture to give an even shade (Two or more coats new work)	270	Sqm	Rs.67.10/-		
7	Dismantling of cement asbestos, celotax or other hard board ceiling and partition walls including stacking of serviceable materials and disposal of unserviceable material within 50 meters lead .	214.29	Sqm.	Rs. 296.70/-		
8	Dismantling of floor/window and doors. i. Carpenter (1st class)	09	Day	Rs.500/-		
9	Dismantling of Puff Panels of side walls, roofing etc (completely including the opening of nuts and bolts)	9020	Sft.	RTQ		
10	Carriage of material from hut site to SASB store Labour	45	Day	Rs.300/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Improvement to the CGI sheet store at Brarimarg .

**S.No. : 25**

**Adv.Cost: 0.60 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Repairs to the steel structure of and CGI sheet roofing by engaging the skilled and semi skilled labour i. Black Smith (1st class) ii. Helper	02 02	Day Day	Rs 450/- Rs.300/-		
2	Dry random rubble stone masonry with hard stone in foundation / plinth and wall using nallah stone without bond stone	10	Cum	Rs.1304.45/-		
3	Providing of stone used for masonry work (quarry)	10	Cum	Rs.280/-		
4	Carriage of stones for a lead of 2 Km (approx.)	350	Cft	RTQ		
5	Fixing of 2 No. doors to the store by engaging the skilled labour (Carpenter)	01	Day	Rs 500/-		
6	Carriage of 02 No. doors from Panjtarni to Brarimarg (Labours)	02	Day	Rs.300/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Construction of BSNL Staff Shed, Labour shed, SASB staff shed and Store for SASB material including its cost of dismantling and stacking after culmination of Yatra at Holy cave

**S.No.: 26**

**Adv.Cost: 0.84 lac**

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes upto 0.1 0cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mm and lift upto 1.5 mtr in all kinds of soil. By manual means.	44	No.	Rs 24.90/-		
2	Fixing available steel structure and wood frames for sheds i. Carpenter ii. Mazdoor	08 06	Day Day	Rs 450/- Rs.300/-		
3	Fixing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m <sup>2</sup> (Labour only)	259	Sqm	Rs 219.82/-		
4	Carriage of material from SASB store to site of work.(Mazdoor)	06	Day	Rs. 300/-		
5	Dismantling of the steel structure of SASB Staff and store shed. i. Carpenter ii. Mazdoor	05 03	Day Day	Rs 450/- Rs.300/-		
6	Taking of door, windows and celestory window shutters including stacking within 50 meter lead.	08	No.	Rs.55/-		
7	Dismantling roofing including ridges, hips, valleys and gutters etc and stacking material within 50 meter lead of G.S. sheet.	210	Sqm.	Rs. 62.25/-		
8	Engagement of labour for shifting of material from site of work to SASB store	10	Day	Rs300/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**



## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Construction of Shoe rack shed (14'x10'), 01 No. frisking shed (size 8'x8' ) and Cloak room including its cost of dismantling and stacking after culmination of Yatra at Holy Cave.

**S.No.: 27**

**Adv.Cost: 0.75 lac**

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes upto 10.0 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mm and lift upto 1.5 mtr in all kinds of soil. By manual means	33	No.	Rs 24.90/-		
2	Fixing wood work in frames of false ceiling, partitions etc sawn and fixed in position. Budloo/Fir wood.	1.52	Cum.	Rs 12755.75/-		
3	Fixing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m <sup>2</sup> (Labour only)	177.21	Sqm	Rs 219.82/-		
4	Engaging labour for shifting of material from SASB store to site of work	14	Day	Rs. 300/-		
5	Dismantling wood work in frames, trusses, purlins and rafters upto 10 m span and 5 meter height including stacking material within 50 meter lead of sectional area below 40 sqm	200	Rm.	Rs 7.05/-		
6	Dismantling roofing including ridges, hips, valleys and gutters etc and stacking material within 50 meter lead of G.S. sheet.	177	Sqm	Rs.62.25/-		
7	Taking of door, windows and celestory window shetters including stacking within 50 meter lead	01	No.	Rs.55/-		
8	Engagement of labour for shifting of material from site of work to store after the dismantling.	14	Day	Rs.300/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Construction of Pandal including its cost of dismantling and stacking after the culmination of yatra at Holy cave.

**S.No. : 28**

**Adv.Cost: 1.50 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Excavating holes upto 0.10 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mtr and lift upto 1.5 mtr in all kinds of soil. By manual means.	10	No.	Rs 24.90/-		
2	Fixing wood work in frames sawn and put up in positions. (Budloo/ Fir wood)	1.95	Cum	Rs.12755.75/-		
3	Fixing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m <sup>2</sup> (Labour only)	419.18	Sqm	Rs.219.82/-		
4	Carriage of Material from store to site of work manually (Mazdoor)	16	Day	Rs.300/-		
5	Dismantling wood work in frames, trusses, purlins and rafters upto 10 m span and 5 meter height including stacking material within 50 meter lead of sectional area below 40 sqm	244	RM.	Rs. 7.05/-		
6	Taking out doors, windows and clerestory window shutters including stacking within 50 m lead.	15	No.	Rs.55/-		
7	Dismantling roofing including ridges, hips, valleys and gutters etc and stacking material within 50 meter lead of G.S. sheet.	419.18	Sqm	Rs.62.25/-		
8	Engagement of labour for shifting of material from site of work to store after the dismantling.	16	Day	Rs.300/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.**

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Erection of barbed wire fencing to medical camps (05 No.0 of size 25'x 50') including cost of its dismantling and stacking after the culmination of Yatra at enroute Domail to Brarimarg.

**S.No. : 29**

**Adv.Cost: 1.37 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Excavating holes upto 0.50cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mm and lift upto 1.5 mtr in all kinds of soil. By manual means.	100	No.	Rs 24.90/-		
2	Providing wood work in frames of false ceiling, partitions etc sawn and fixed in position. Budloo/Fir wood	66	Cft	RTQ		
3	1.8m high fencing with 2.5 m Sal bali posts, 30cms girth (min)placed every 2.5 m apart embedded in cement concrete blocks, every 15 <sup>th</sup> post, last but one end post and corner post shall be strutted on both sides and end post on side only, provided with 9 horizontal lines and two diagonals of barbed wire 9.38 Kg per 100m (Min) between two posts filled and fixed with G.I staples driven into the posts,including two coats of coal tarring of ballies complete. (Cost of posts, struts,earthwork and concrete to be paid for separately). With G.I barbed wire.	2.65	Rm	Rs153.90/-		
4	Carriage of material by mechanical means from Srinagar to Domail Trips of LMV	04	No.	RTQ		
5	Carriage of material by from Domail to Brarimarg by head load (Porters)	60	No.	RTQ		
6	Dismantling of barbed wire fencing and wooden posts including carriage and stacking at nearest SASB store (Mazdoor)	30	Day	Rs.300/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Bidder**

**DGM (W) Baltal**

**Signature of the**



## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Installation of sign boards and informatory boards including cost of its dismantling, carriage and stacking after the culmination of Yatra enroute Domail to Holy cave and Sangam to Panjtarni

**S.No.: 30**

**Adv.Cost: 0.60 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Fixing of the sign boards or information boards at different locations Mazdoor	25	Day	Rs.300/-		
2	Carriage of boards from SASB store (Baltal/Domail) to various site of installation. Porters	25	No.	RTQ		
3	Dismantling of the sign Board or information boards from different locations including carriage of dismantled material (boards) to SASB store. i. Mazdoor ii. Porters	13 25	Day . No.	Rs.300/- RTQ		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Assembling of railing along the stairs, around the Nandi Point and erection of entrance gate including cost of its dismantling and proper stacking after the culmination of yatra at Holy cave.

**S.No. : 31**

**Adv.Cost: 1.30 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Laying and fitting of G.I pipes complete excluding the cost of pipes of 40mm dia.	1800	Rm	Rs.27.40/-		
2	Erection of detachable mild steel posts for railing pipes. i. Black Smith (1st class) ii. Helper	08 08	Day Day	Rs.450/- Rs.300/-		
3	Erection of railing around Nandi point. i. Black Smith (1st class) ii. Helper	01 01	Day Day	Rs.450/- Rs.300/-		
4	Erection of entrance gate at Holy Cave. i. Black Smith (1st class) ii. Helper	02 02	Day Day	Rs.450/- Rs.300/-		
5	Carriage of material (pipes,gat es railing posts) from SASB store to site of work. Mazdoor	16	Day	Rs.300/-		
6	Dismantling of railing post,railing around Nandi point & entrance gate i. Black Smith (1st class) ii. Helper	06 06	Day Day	Rs.450/- Rs.300/-		
7	Dismantling of G.I pipes complete excluding the cost of pipes of dia 40mm (Half rate of erection )	1800	Rm	RTQ		
8	Carriage of material from site of work to SASB stores after the conclusion of yatra. Mazdoor	16	Day	Rs.300/-		

**Total cost of bid (to be quoted both in figures and words)**

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Assembling of 3 No. wooden foot – bridges including cost of its dismantling and stacking properly after the completion of Yatra at Kali Mata Track

**S.No. : 32**

**Adv.Cost: 0.80 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Fixing of wood as a wooden joist on the well prepared abutments of the 1st, 2nd and 3rd bridge.  i. New Wood ii. Old wood	0.186 0.744	Cum Cum	Rs 42755.75/- Rs.12755.75/-		
2	Fixing of wood as flooring, railing struts, bracings etc including the cost of nails at its appropriate position.  i. New Wood ii. Old wood	0.237 0.952	Cum Cum	Rs 42755.75/- Rs.12755.75/-		
3	Carriage of wood from Brarimarg SASB store to site of installation	18	Day	Rs.300/-		
4	Carriage of New wood from Domel to site of installation (Kali Mata track) Ponies	06	No.	RTQ		
5	Carriage of wood from Srinagar to Domel by M.T.	0.423	Cum	Rs.811.54/-		
6	Dismantling wood work in frame, trusses, purlins and rafters upto 10 M span and 5 metres height including stacking the material within 50 m lead.	2.12	Cum	Rs.1767.10/-		
7	Carriage of bridge from bridge site to SASB store at Brarimarg	18	Day	Rs.300/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Fixing and painting of railing post and railing pipes including fixing of barriers, laying and painting of milestone including cost of its Dismantling at Kali Mata Track.

**S.No. : 33**

**Adv.Cost: 3.25 lac**

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Laying and fitting of G.I. Pipes complete excluding the cost of pipes and earthwork 40 mm dia nominal bore (medium) including carriage also	2412	Rm.	Rs 27.40/-		
2	Fixing of Mild steel barrier at Kali Mata Track with nuts and bolts. i. Black Smith (1st class) ii. Helper	04 04	Day Day	Rs.450/- Rs.300/-		
3	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade <b>G.I. posts</b> on Old steel work (one or more coat) On New steel work (two or more coats) <b>G.I. Pipes</b> On old pipes of dia 40 mm (one or more coat) On New steel work (Two or more coats)	51.84 237.60  107.25 195.36	Sqm Sqm  Sqm Sqm	Rs.45.60/- Rs.69.30/-  Rs.45.60/- Rs.69.30/-		
4	Laying and fitting of the posts to the base (detachable posts with nuts and bolts) i. Black Smith (1st class) ii. Helper	22 22	Day Day	Rs.450/- Rs.300/-		
5	Providing one thin coat with white lead of approved brand and manufacture on the plastered surface of Km stones.	5.6	Sqm	Rs.44.70/-		
6	Carriage of 120 no.new 40 mm dia railing pipes from Domel to Kali Mata track (porters)	120	No.	RTQ		
7	Dismantling of the G.I pipes complete excluding the cost of pipes and earth work 40mm dia nominal bore including carriage from site to SASB store. (Under rate /half rate of erection )	2412	Rm	RTQ		
8	Dismantling of the G.I. iron posts from its base and carriage of parts from site to store i. Black Smith (1st class) ii. Helper	17 17	Day Day	Rs.450/- Rs.300/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Painting to Prefabricated Toilets/Baths enroute Domail to Holy Cave (70 No.)

**S.No. 34**

**Adv.Cost: 0.95 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc (40%)	580	Sqm	Rs.6.75/-		
2	Applying priming coat with ready mixed red oxide Zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works. (40%)	580	Sqm	Rs.27.80/-		
3	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade on old steel work ( one or more coat) (100%)	1450	Sqm	Rs.45.60/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Painting to Prefabricated Toilets/Baths at Holy Cave ( 100 No.)

**S.No. 35**

**Adv.Cost: 1.50 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc (40%)	830	Sqm	Rs.6.75/-		
2	Applying priming coat with ready mixed red oxide Zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works. (40%)	830	Sqm	Rs.27.80/-		
3	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade on old steel work ( one or more coat) (100%)	2076	Sqm	Rs.45.60/-		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Painting and repair to grill and counting hall at Holy Cave

**S.No. : 36**

**Adv.Cost: 0.30 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Removing white or colour wash by scraping and sand papering and preparing the surface smooth including necessary repairs to scratches etc complete.	190	Sqm	Rs 6.75/-		
2	Painting of grill with synthetic enamel paint of approved brand & manufacture of required colour to give an even shade( one or more coats on old work).	130	Sqm	Rs 45.60/-		
3	Painting of wall below the grill with epoxy paint of all locations prepared and applied as per manufacture specifications including appropriate priming coat, preparation of surface etc. complete on concrete work.	60	Sqm	Rs.128.95/-		
4	Repair to the counting hall at Holy Cave. i. Carpenters ii. Helpers	06 06	Day Day	Rs.500/- Rs.300/-		
5	Painting to the counting hall with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade (one or more coats on old wall).	60	Sqm	Rs.45.65/-		
6	Carriage of Paint from Domel Holy Cave by head load. (Porters)	02	No.	RTQ		

**Total cost of bid (to be quoted both in figures and words)**

**Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.**

**Signature of the Bidder**

**DGM (W) Baltal**

## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Clearance of snow (with frost ) from Stairs, Helipad and track from helipad to upstairs at Holy Cave

**S.No. : 37**

**Adv.Cost: 3.40 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Clearing snow (with frost) from tracks, manually using picks and shovels					
	i. Helipad	1350	Cum	RTQ		
	ii. Track from Helipad to upstairs	240	Cum	RTQ		
	iii. Stairs	4818	Cum	RTQ		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**



## **SCHEDULE – B (Format for Financial Bid)**

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

### **Rate List/ Quantity Schedule**

**Name of Work:** Clearance of snow (with frost ) from Kali Mata Track

**S.No. : 38**

**Adv.Cost: 1.55 lac**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate as per SSR of 2012</b>	<b>Rate to be quoted by the Bidder (above/ below %age)</b>	<b>Amount</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>	<b>VII</b>
1	Clearing snow (with frost) from tracks, manually using picks and shovels.	2940	Cum	RTQ		
<b>Total cost of bid (to be quoted both in figures and words)</b>						

**Note:** Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

**Signature of the Bidder**

**DGM (W) Baltal**